

**SURVEY & REMONUMENTATION**

NOV-10 1997

**LAND CORNER RECORDATION CERTIFICATE**  
**COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

97 OCT 15 PM 12:13

REGISTER OF DEEDS

*Kay S. ...*  
 SHIAWASSEE COUNTY, MICH.

For corners in Shiawassee (County) Located In: Fairfield Twp Corner Code # \_\_\_\_\_

1. Public Land Survey T 8N R 1E D-2  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Wendy A. Papineau, in a field survey on June 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

D-2 Closing 1/4 Corner, Section 5, T8N-R1E

This position was not established by original government survey.

Shiawassee County Survey by Lyman Mason, June 1876. Recorded in Book D, Pgs 118-119, S.C.D.R.  
 N52 1/2W 31 lks (20.46') 40" Sycamore  
 N61E 65 lks (42.90') 8" B. Oak

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

D-2 Closing 1/4 Corner, Section 5, T8N-R1E

Found no evidence of corner or witnesses.

County Survey measurement between D-1 and D-3, T8N-R1E was 79.29 ch (5233.14'). Today's measurement is 5246.11' (66.16'/ch). This chainage is consistent with ties to found monumentation and occupation as shown on Mason's survey. Calculated a position using a proration for the mile against the South 1/2 mile. This position fits occupation and monuments to the East, with the exception of a found wood post near the easterly road right of way, which falls 7.8' South.

This position is accepted as the best available evidence of the position of the corner.

Approved by the Shiawassee County Remonumentation Peer Review Group September 4, 1997.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

D-2 Closing 1/4 Corner, Section 5, T8N-R1E

Placed a standard Harrison monument on the Michigan Meridian.

S10W 146.15' Set PK w/tag #39096 E. fc P/P  
 S85E 45.57' Set PK w/tag #39096 S. fc 6" wood fnc post  
 N45W 43.91' Set spike w/tag #39096 S. fc 5" Oak  
 N75W 37.82' Set spike w/tag in S. fc of 4" Oak

**APPROVED**

County Remonumentation  
 Peer Review Group

Signed by Wendy A. Papineau

Date 10-09-97

Surveyor's Michigan License No. 41919



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983  
 ADAPTED FOR WORD PROCESSING MARCH, 1993

**LIBER LR PG 190**

