

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &
 REMONUMENTATION

NOV 03 1998

For corners in

Shiawassee
 (County)

Located in:

Corner Code #

1. Public Land Survey

T 8N R 2E

K-10

2. Property Controlling
 In Section

S T R

3. Miscellaneous
 Property in Sec.

S T R

4. Lot No. _____

S T R

5. Private Claims _____

S T R

Recorded Plat _____

SECTION

Register of Deeds Stamp
 & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	1	2	3	4	5	6	7	8	9	10	11	12	13
3	4	5	6	7	8	9	10	11	12	13	14	15	16
4	5	6	7	8	9	10	11	12	13	14	15	16	17
5	6	7	8	9	10	11	12	13	14	15	16	17	18
6	7	8	9	10	11	12	13	14	15	16	17	18	19
7	8	9	10	11	12	13	14	15	16	17	18	19	20
8	9	10	11	12	13	14	15	16	17	18	19	20	21
9	10	11	12	13	14	15	16	17	18	19	20	21	22
10	11	12	13	14	15	16	17	18	19	20	21	22	23
11	12	13	14	15	16	17	18	19	20	21	22	23	24
12	13	14	15	16	17	18	19	20	21	22	23	24	25
13	14	15	16	17	18	19	20	21	22	23	24	25	26

I, Mark L. VanRaemdonck, in a field survey on June 22, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- Original, William Brookfield, D.S., December 1823
 Monument: Wood post
 Accessories: Beech 12 S4½°E 10
 do 10 N25°E 20
- Mark L. VanRaemdonck, LCRC recorded L 2, page 129, October 18, 1978
 Monument: Found RR spike
 Accessories: East 30.73' Set PK in 14" Maple
 S30°E 51.85' Set PK in 18" Oak
 N85°W 38.12' Set PK in pole
 West 10.00' ← Physical centerline pavement
- Mark L. VanRaemdonck, Certified Survey, recorded L 7, page 702, November 5, 1996
 Monument: Found RR spike
 Accessories: West 13.0' centerline asphalt
 S60°W 34.04' N end 12" conc. curv.
 N87°W 36.10' PK N face util. pole

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
 Found railroad spike as referenced in No. 2 and No. 3 above. I accepted this location as the original corner position based on the best available evidence. During excavation for Harrison Marker, I found stones and a ½" pipe. I removed the stones and drove the pipe lower. The pipe is on the SE edge of the bottom of the Harrison Marker. Found no conflicting evidence.

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:
 I replaced the rerod and cap with a standard Shiawassee County Harrison Marker Monument, stamped "Remon P.S. 24622" and witnessed by the following accessories:

- | | | |
|-------|--------|-----------------------------------|
| N85°W | 36.30' | PK in N face util. pole |
| N60°W | 36.83' | Top cen. S end 12" CMP curv. |
| S30°W | 60.55' | Top cen. S end 12" conc. curv. |
| S85°W | 19.10' | Top of wood post (10") in asphalt |
| West | 13.60' | centerline of asphalt surface |

Signed by Mark L. VanRaemdonck
 Surveyor's Michigan License No. 24622

Date SEPT. 18, 1998

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS
 JAN 18, 1971
 REVISED MAY 14, 1976
 REVISED JAN., 1983



Kaye Grubba - Shiawassee Co.

REMON

3007697
 Page: 1 of 1
 10/27/1998 03:22P

Lb-1 Pg-250

APPROVED

County Remonumentation
 Peer Review Group

NCC 7 OCT 98

