

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &
 REMONUMENTATION

For corners in

NOV 03 1998

SECTION

<u>Shiawassee</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>2E</u>	<u>L-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

**Register of Deeds Stamp
 & File Number**



3007698
 Page: 1 of 1
 10/27/1998 03:22P
 Lb-1 Pg-251

I, Mark L. VanRaemdonck, in a field survey on June 22, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1. Original, William Brookfield, D.S., December 1823
 Monument: Wood post
 Accessories: W Oak 40 East 38LKS B Oak 24 N5°W 30
2. Andre Huggins, County Surveyor, County Surveyors Book B, page 61, August 1855
 No monument or accessories are given.
3. Ezra Mason, County Surveyor, County Surveyors Book A, page 244-245, August 5 & 6, 1872
 No monument or accessories are given.
4. O.M. Elliot, County Surveyor, Book CR 174, page 55, no date.
 Monument: Not given.
 Accessories: S30°W 23.53' 18" Maple N50°E 29.30' 20" Hickory
 N20°W 23.11' 15" Maple North 23.60' corner fence post
5. John Quine, County Surveyor, Book G, 10/23/66
 Monument: 1 1/2" iron Accessories: Same as No. 4 above
6. Mark L. VanRaemdonck, Certified Survey, recorded Liber 3, page 37, June 9, 1978
 Monument: Found 1 1/2" iron bar
 Accessories: South 32.40' 3/4" pipe in conc. N10°W 23.53' PK in 14" Maple
 S20°W 23.35' PK in 18" Maple N30°E 29.55' PK in 24" Maple
7. Mark L. VanRaemdonck, Certified Survey, recorded Liber 3, page 92, September 18, 1978
 Monument and accessories same as No. 6 above.
8. Mark L. VanRaemdonck, LCRC, recorded Liber, page 129, October 18, 1978
 Monument and accessories same as No. 6 above.
9. Mark L. VanRaemdonck, Certified Survey, recorded Liber 3, page 214.
 Monument and accessories same as No. 6 above.
10. Mark L. VanRaemdonck, Certified Survey, recorded Liber 3, page 291.
 Monument and accessories same as No. 6 above.
11. Mark L. VanRaemdonck, Certified Survey, recorded Liber 3, page 272, November 29, 1979
 Monument and accessories same as No. 6 above.
12. Mark L. VanRaemdonck, Certified Survey, recorded Liber 3, page 592, February 2, 1982.
 Monument and accessories same as No. 6 above.
13. Mark L. VanRaemdonck, Certified Survey, recorded Liber 4, page 491, September 25, 1986
 Monument: Found 1 1/2" steel pin
 Accessories: N30°E 29.00' PK S face 18" Maple S05°W 22.50' PK E face 18" Maple
 S02°E 49.36' PK E face T/P S60°E 55.95' PK E face 18" Maple
14. Mark L. VanRaemdonck, Certified Survey, recorded Liber 4, page 637, September 23, 1987
 Monument and accessories same as No. 13 above.
15. Norm Caldwell, LCRC, recorded Liber 2, page 658, August 3, 1989
 Monument and accessories same as No. 6 above.
16. Norm Caldwell, LCRC, recorded Liber 5, page 302, August 3, 1989
 Monument and accessories same as No. 6 above.
17. Mark L. VanRaemdonck, Certified Survey, recorded Liber 6, page 248, August 13, 1992
 Monument and accessories same as No. 13 above.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	20	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

APPROVED

County Remonumentation
 Peer Review Group

NCC 7 OCT 98

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
 Found 1 1/2" steel pin, bent to South, as referenced in No. 4, No. 6 and No.13 above. Found large stones around pin.
 Found no conflicting evidence. I accepted this location as the original corner position based on the best available evidence.

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

I replaced the 1 1/2" steel pin described above with a Standard Shiawassee County Harrison Marker Monument, stamped "Remon P.S. 24622" as witnessed by the following accessories:

S02°E 49.08'	N&T 24622 W face util. pole	South	31.98'	Old 3/4" pipe in conc.
S20°W 27.98'	N&T 24622 W face 24" Maple	S70°W	56.70'	N&T 24622 N face 30" Maple
N40°E 29.87'	N&T 24622 SE face 30" Hickory	North	24.50'	anchor post (down)

Signed by Mark L. VanRaemdonck
 Surveyor's Michigan License No. 24622

Date SEPT. 21, 1998