

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Cor 1

For corners in SECTION

Shiawassee
 (County)

Located in:

Corner Code #

1. Public Land Survey

T 8N R 2E
 T R
 T R
 T R

M-8



3026131
 Page: 1 of 1
 10/05/1999 02:19P
 L-1 P-324

2. Property Controlling in Section

S T R
 S T R

3. Miscellaneous Property in Sec.

S T R
 S T R

4. Lot No.

Recorded Plat

5. Private Claims

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	5	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	18	15	14	13						
7												
8	19	20	21	22	21	20						
9												
10	23	23	23	27	28	25						
11												
12	31	32	31	34	35	36						
13												

I, Mark L. VanRaemdonck, in a field survey on February 15, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1. Original, Joseph Wampler, D.S., 1823.
 Mon: Wood Post
 Accessories: Beech 16 S2¼°E 38
 Do 11 N33°W 12

2. E.L. Mason, County Surveyor, County Surveyor's Book B, page 84, (no date). Breakdown of Section 24, T8N-R2E. No monument or accessories given.

3. Ezra Mason, County Surveyor, County Surveyor's Book C, page 154, Book A, page 24. Breakdown of Section 24, T8N-R2E, December 22 and 23, 1868. No monument or accessories given.

4. C.E. Smith, M.D.S.H., Survey Chief, July 1962.
 Mon: Found nail in M-47 from survey of land. Put Ackerman (lead plug) in pavement below asphalt.
 Accessories: SE 68.25' to W1/4 cor. Sec. 19, T8N-R2E
 T. Pole S20°W 92.00'
 20' Apple S55°W 26.55'
 25' Elm West 44.55'
 SE cor. H. wall S50°W 11.90'
 SW cor. E. h. wall N70°E 27.80'

5. John Quine, Certified Survey, (unrecorded), November 29, 1966.
 Mon: Lead plug in mon. box
 Accessories: None given.

6. John Quine, L.C.R.C., recorded in Liber 1, page 521, March 25, 1975.
 No monument or accessories given.
 Refers to M.D.S.H. plans for M-52.

7. Mark L. VanRaemdonck, Certified Survey, Recorded Liber 6, page 942, September 15, 1994.
 Mon: Boat spike in mon. box
 Accessories: South 68.27' Center mon. box
 N70°E 53.53' Chiseled '+' top cen. conc. hdwl.
 N70°W 36.41' Chiseled '+' top cen. conc. hdwl.
 East 8.30' CL M-52

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
 Found boat spike in mon. box, as referenced in No. 4 and 7 above. I accepted this location as the original corner position based on the best available evidence. Found no conflicting evidence.

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:
 Replaced boat spike with a standard Shiawassee County Harrison Marker monument. The monument is stamped "REMON P.S. 24622" and is witnessed by the following accessories:

N70°W 36.40' '+' Top cen. conc. Headwall
 N65°W 55.92' Set N&T E. face E. leg billboard
 S05°43'07"E 2630.05' Harrison Marker @ M-9
 N65°E 53.23' '+' Top cen. conc. Headwall
 East 8'± CL asphalt M-52
 N00°38'40"W 2622.00' Harrison Marker @ M-7

Signed by Mark L. VanRaemdonck
 Surveyor's Michigan License No. 24622

Date SEPT. 23, 1999

APPROVED
 County Remonumentation
 Peer Review Group
 100793
 MCC

