

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

SURVEY &  
 REMONUMENTATION

NOV 03 1998

For corners in

<u>Shiawassee</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>2E</u>	<u>M-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____	Recorded Plat _____	_____
5. Private Claims _____		_____

SECTION

**Register of Deeds Stamp  
& File Number**

I, Mark L. VanRaemdonck, in a field survey on June 22, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	20	29	28	27	26	25							
11													
12	21	22	23	24	25	26							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

- Original, William Brookfield, D.S., December 1823  
 Monument: Wood post  
 Accessories: W Oak 30 N29°W 31  
 do 30 S24°E 39
- Andrew Huggins, County Surveyor, County Surveyors Book B, page 61, August 1855  
 No monument or accessories are given.
- Ezra Mason, County Surveyor, County Surveyors Book A, page 244-245, August 5 & 6, 1872  
 Monument: not given  
 Accessories: S Maple 10 N26°E 52
- O.M. Elliot, County Surveyor, Field Book CR 174, page 55, no date.  
 Monument: Not given.  
 Accessories: Sketch shows a distance of 2614.92 feet to the NE corner of Section 25.
- John Quine, County Surveyor, Book G, 10/23/66  
 Monument: 1 1/2" Iron  
 Accessories: Same as No. 4 above

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

Found no evidence of original monument or accessories. Found no evidence of subsequent restoration. The corner is lost. I re-established this location using the single proportional method between corners M-9 and M-11, T8N-R2E. The measured distance between M-9 and M-10, 2615.08 feet, fits well with the distance given in Elliot's field book (No. 4 above) 2614.92 feet. Found no conflicting evidence. I accepted this location as the careful and faithful re-establishment of the original corner location.

**C. Description of monument for corner and accessories to perpetuate locating the position of the corner:**

At the above described location, I installed a standard Shiawassee County Harrison Marker Monument, stamped "Remon P.S. 24622" and witnessed by the following accessories:

- |              |  |
|--------------|--|
| West 32.60'  | Rerod & cap #24622 on West bank of drain on S side of steel fence post |
| North 67.40' | S edge of steel fence post on East bank of ditch                       |
| West 16'+-   | centerline of Huckleberry Mitchner Drain                               |
| N00°21'39"W  | 2615.06' Harrison Marker at corner M-9                                 |
| S00°21'39"E  | 2615.08' Harrison Marker at corner M-11                                |
| West 3.00'   | Carsonite marker   |

NOTE: The Harrison Marker was installed 12 inches +/- below the surface of the ground to avoid damage by farm equipment.

Signed by Mark L. VanRaemdonck  
 Surveyor's Michigan License No. 24622

Date SEPT 18, 1998

