

APR 08 1996

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

COMMISSION

Shiawassee  
(County)

Located in:

Corner Code #

- 1. Public Land Survey T 8N R 2E (M-11)  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
In Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property In Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

RECORDED

95 NOV 22 PM 1:20

REGISTER OF DEEDS

*Wayne Hubbard*

SHIAWASSEE COUNTY, MICH.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Mark L. VanRaemdonck, in a field survey on October 18, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the current points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1.) Original: Joseph Wampler, D.S.  
Monument: Wood stake  
Accessories: Birch 14 S85°W 9  
Sugar 9 N48°E 28
- 2.) C.E. Smith, M.D.O.T., July 1962  
Monument: Found 2" wood stake. Put in 1" iron rod  
Accessories: 14" Box Elder S20°E 77.88'  
SE corner Wingwall N30°E 67.30'  
T. pole S70°W 60.59'  
123.87' North to SW corner Section 30,  
T8N-R3E  
(GLO = 1.87 ch. = 123.42)
- 3.) M. VanRaemdonck, Survey recorded Liber 3, page 225, 6/14/79  
Monument: Found 5/8" rerod  
Accessories: N10°W 82.70' Road sign  
N60°E 67.10' SW cor. SW wingwall  
S70°W 60.59' Power pole  
S20°E 77.88' 14" Box Elder
- 4.) M. VanRaemdonck, L.C.R.C. recorded Liber 2, page 199, 9/5/79  
Monument: Found 5/8" rerod  
Accessories: Same as no. 3 above
- 5.) M. VanRaemdonck, Survey recorded Liber 6, page 945, 8/13/93  
Monument: 1/2" rerod with cap #24622  
Accessories: Same as no. 3 above.
- 6.) M. VanRaemdonck, Survey recorded Liber 6, page 795, 8/13/93  
Monument: 1/2" rerod with cap #24622  
Accessories: Same as no. 3 above

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" rerod with cap #24622 as referenced in no.'s 3, 4, 5 and 6 above. Checked with references in no. 2 above. Found no conflicting evidence. Found brick, crockery, broken plates, pieces of glass and scrap iron during excavation for Harrison Marker. Accepted this location as the careful and faithful perpetuation of the original corner location.

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

Replaced rerod and cap with standard Harrison Marker stamped "REMON 24622" and witnessed by the following accessories:  
S65°W 60.46' Set N&T 24622 N. face utl. pole  
S20°E 57.52' Set N&T 24622 NE face 10" Elm  
N45°E 46.34' Top cen. tele. cable box  
N35°E 67.11' SW edge SW cor. of W. conc. wingwall  
North 123.45' Pipe at SW cor. Section 30, T8N-R3E

APPROVED

County Remonumentation  
Peer Review Group

OCT 24, 1995 MLV

Signed by *Mark L. VanRaemdonck*

Date *Nov 16, 1995*

Surveyor's Michigan License No. 24622

