

APR 08 1996 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

Shiawassee Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey T 8N R 2E _____ (M-12)
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property In Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

RECORDED
 95 NOV 22 PM 1:20
 REGISTER OF DEEDS
Gayle Hubbard
 SHIawassee COUNTY, MICH.
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5			4		3		2		1		
3													
4	7	8			9		10		11		12		
5													
6	18	17			16		15		14		13		
7													
8	19	20			21		22		23		24		
9													
10	30	29			28		27		26		25		
11													
12	31	32			33		34		35		36		
13													

I, Mark L. VanRaemdonck, in a field survey on October 18, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the current points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- Original: Joseph Wampler, D.S.
 Monument: Wood stake
 Accessories: Sugar 14 S17°W lks
 Lynn 18 N45°E 3½ lks
- E.F. Joslin, Book N, page 59, 5/11/1904
 Monument: Not given
 Accessories: West ¼ post Section 31, T8N-R3E North 100 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found ¼" x 1½" steel bar at West ¼ corner Section 31, T8N-R3E. Re-established corner location on line between steel bar and Southeast corner Section 36 at 66.00 feet South of steel bar, as per Joslin record. This location fits occupied East and West ¼ line running West. Found no conflicting evidence. Excavation for Harrison Marker provided no further evidence. Accepted this location as the careful and faithful re-establishment of the corner location using the best available evidence.

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

Set a standard Harrison Marker at the location described above. The marker is stamped "REMON 24622" and is witnessed by the following accessories:
 N15°E 65.24' Set N&T 24622 in NW corner R.R. tile fence post
 N60°E 18.60' W. edge steel "T" fence post
 S60°E 18.87' W. edge steel "T" fence post
 North 66.00' ¼" x 1½" flat steel bar at West ¼ corner Section 30, T8N-R3E

APPROVED

County Remonumentation
 Peer Review Group

Signed by Mark L. VanRaemdonck

Date Nov. 16, 1995

Surveyor's Michigan License No. 24622



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS JAN 16, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983