

267

corp

SECTION

1999 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in



3026102  
Page: 1 of 1  
10/05/1999 02:19P  
L-1 P-295

Kaye Grubbs - Shiawassee Co. REMON

Shiawassee Located In: Corner Code #  
(County) New Haven Twp

- 1. Public Land Survey T8N R 3E K-7
- 2. Property Controlling S      T      R       
in Section S      T      R
- 3. Miscellaneous S      T      R       
Property in Sec. S      T      R
- 4. Lot No.      Recorded Plat
- 5. Private Claims

**APPROVED**  
County Remonumentation  
Peer Review Group  
1 OCT 99  
NCC

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John H. Rauser, P.S., in a field survey on August 23 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

**K-7 Section Corner, Sections 13,14,23 & 24, T8N-R3E, New Haven Township, Shiawassee County**  
 1822 Wood post placed by J. Wampler, D.S., Beech 10" N54 1/2 E 13lks (8.58'); Lynn 14" N66W 17lks (11.22')  
 1865 County Survey by Ezra Mason, C.S. Book "C", P. 38-39, no object given, measured to K-8 38.30ch (2527.8').  
 1887 County Survey by H.C. Main, C.S. witnessed corner N40E 151lks (99.66') 6" Sugar; S45W 69lks (45.54') SW cor fnc measured to K-8 38.25ch (2524.5'). Shia. Co. Survey Rec. 1879-1900.  
 1975 Act 132 by D.T. Rowe, P.S. 11192, L. 2, P. 221, set re-rod 0.2' below road surface, witnessed by S45E 69.08' PK w/tag NW fce P/P; N60W 131.15' PK w/tag in blaze of 18" Hickory; S45W 46.00' rerod w/cap #11192  
 1975 Act 74 by J.S. Fokens, P.S. 21567, set 1/2" X18" re-rod w/cap #11192 at corner established by retracement of a survey H. L. (sic) Main, dated February and March, 1887, same witnesses as on 1975 Act 132.  
 1992 Act 132 by M.L. Vanraemdonck, P.S. 24622, found re-rod, S50E 69.15' N&T NW fce P/P; N30E 57.60' S fce cable sign post; S70W 33.43' N fce road sign post; N50W 84.52' E fce cable sign post. L.6, P. 346, SCR.  
 1995 Act 132 by M.L. Vanraemdonck, P.S. 24622, found re-rod, S50E 69.15' N&T NW fce P/P; N30E 57.60' S fce cable sign post; S70W 33.43' N fce road sign post; N50W 84.52' E fce cable sign post., measured to K-8 2509.66'. L.7, P. 363, SCR  
 1998 Act 132 by J.H. Rauser, P.S. 39096, found 1/2" rod, S45E 69.03' PK w/tag NW fce P/P; S65W 34.72' N edge stop sign post; N40W 83.19' top center tele riser; N25E 52.85' top center tele riser; measured to K-8 2509.73' and to L-7 2611.88'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

**K-7 Section Corner, Sections 13,14,23 & 24, T8N-R3E, New Haven Township, Shiawassee County**  
 Found no evidence of original government accessories or county survey accessories. Found 1/2" re-rod with no cap. Corner falls in the approximate centerline of Kerby and Henderson Roads. Found no conflicting evidence in the area of this corner. Measured 2611.88 feet to L-7 and 2509.72 feet to K-8. Check witness from 1975 Act 74 to present. We recommend accepting the found 1/2" re-rod as the best available evidence of the position of the original government corner and replacing it with a standard Shiawassee County Harrison monument 0.5' below grade in the gravel road.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**K-7 Section Corner, Sections 13,14,23 & 24, T8N-R3E, New Haven Township, Shiawassee County**  
 Set a standard 20" Harrison monument at the position approved by the Shiawassee County Peer Review Group.  
 S45°E 69.03' PK & Disk NW fc PP (1975 = 69.08'; 1992 = 69.15'; 1998 = 69.03')  
 S65°W 34.72' N edge new stop sign post (R&M = S70W, 33.4' old base of cut off post in concrete)  
 N40°W 83.19' Top center tele. riser (1998 = 83.2')  
 N25°E 52.85' Top center tele. riser (1998 = 52.8')  
 N30°E 57.60' S. face cable sign post (1992 = 57.6')  
 N60°W 130.7' SE face 20" Hickory (1975 = 131.15' to PK)  
 N50°W 84.3' E. face cable sign post (1992 = 84.52')

Signed by John H. Rauser  
 Surveyor's Michigan License No. 39096



9/9/99