

**SURVEY & REMONUMENTATION**

Car 1

**1999 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in



3026103  
Page: 1 of 1  
10/05/1999 02:19P  
L-1 P-296

Keye Grubba - Shiawassee Co. REMON

Shiawassee Located In: New Haven Twp Corner Code #

- |                                    |     |      |     |
|------------------------------------|-----|------|-----|
| 1. Public Land Survey              | T8N | R 3E | K-8 |
|                                    | T   | R    |     |
| 2. Property Controlling in Section | S   | T    | R   |
|                                    | S   | T    | R   |
| 3. Miscellaneous Property in Sec.  | S   | T    | R   |
|                                    | S   | T    | R   |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

**APPROVED**  
County Remonumentation Peer Review Group  
100799  
MCC

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John H. Rauser, P.S., in a field survey on August 23 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management, or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

**K-8** 1/4 Corner, Sections 23 & 24, T8N-R3E, New Haven Township, Shiawassee County  
1822 Wood post placed by J. Wampler, D.S., Elm 16" S16 1/2 W 26lks (17.16'); Ash 10" N10W 8lks (5.28')  
1865 County Survey by Ezra Mason, C.S. Book "C", P. 38-39, no object given, measured to K-7 38.30ch (2527.8').  
1887 County Survey by H.C. Main, C.S. witnessed corner N68 1/4W 63 3/4 lks (41.91') 20" S Maple; N80 1/2W 47 1/2 lks (31.35') 8" Elm; measured to K-7 38.25ch (2524.5') and to K-9 40.16ch (2650.56'). Shia. Co. Survey Rec. 1879-1900.  
1975 Act 74 by J.S. Fokens, P.S. 21567, set 1/2" X18" re-rod w/cap #11192 at the intersection of the E & W 1/4 line as occupied and the physical centerline of Kerby Road. L.1, P. 630. Witnesses West 19.55' Chis "+" top 15" CMP; East 20.75' notch top end 15" CMP.  
1995 Act 132 by M.L. Vanraemdonck, P.S. 24622, re-rod & cap 24622, N75W 27.00' t/c tele cable box; East 20.80' t/c E end 18" CMP; S25W 39.68' t/c S. end 12" conc culv; West 19.72' t/c W end 18" CMP. measured to K-9 2659.52'. L. 7, P. 362  
1995 Act 132 by M.L. Vanraemdonck, P.S. 24622, same object and witnesses as previous, measured to K-7 2509.66' L.7, P. 363, SCR  
1998 Act 132 by J.H. Rauser, P.S. 39096, found 1/2" rod w/ cap 24622, East 20.59' Chis "+" t/c E end 15" CMP; West 19.57' Chis "+" t/c W end CMP; N70W 26.89' t/c tele riser; N40E 27.69' Set rod w/ cap #39096 in road shoulder, measured to K-7 2509.73'. Liber 8, P. 347

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

**K-8** 1/4 Corner, Sections 23 & 24, T8N-R3E, New Haven Township, Shiawassee County  
Found no evidence of original government accessories or county survey accessories. Culvert construction has probably destroyed any evidence from the past records. Found 1/2" re-rod with cap #24622. Corner falls in the approximate centerline of Kerby Road. Found no conflicting evidence in the area of this corner. Measured 2659.62 feet to K-9 and 2509.72 feet to K-7. Checked witness from 1975 Act 74 to present. We recommend accepting the found 1/2" re-rod as the best available evidence of the position of the original government corner and replacing it with a standard Shiawassee County Harrison monument 0.5' below grade in the gravel road.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**K-8** 1/4 Corner, Sections 23 & 24, T8N-R3E, New Haven Township, Shiawassee County  
Set a standard 20" Harrison monument at the position approved by the Shiawassee County Peer Review Group.  
East 20.59' Chisled "x" top E. end 15" CMP  
West 19.57' Chisled "x" top W. end 15" CMP  
N70°W 26.89' Top center telephone riser  
N40°E 27.69' Set rod w/cap #39096 in road shoulder

Signed by John H. Rauser  
Surveyor's Michigan License No. 39096

