

1998 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

NOV 03 1998

SECTION

For corners in

Shiawassee
(County)

Located In: New Haven Twp
Corner Code #



3007716
Page: 1 of 2
10/27/1998 03:22P
Lb-1 Pg-269

Kaye Grubba - Shiawassee Co. REMON

- | | | | |
|---------------------------------------|--------------|--------------|------------|
| 1. Public Land Survey | T <u>8 N</u> | R <u>3 E</u> | K <u>9</u> |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| 2. Property Controlling
in Section | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |
| 3. Miscellaneous
Property in Sec. | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John H. Rauser, P.S., in a field survey on February 20, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-9 Section Corner, Sections 23,24,25 & 26, T8N-R3E, New Haven Township

- 1822 G.L.O. Joseph Wampler, D.S., 10" Elm at corner No accessories given
1887 Surveys by H. C. Main, C.S.; Stake & Stone, measured 40.94 ch. between K-9 and K-10, measured 40.16 ch between K-9 and K-8, measured 40.75 ch. between K-9 and J-9.
N31 3/4W 88.5 lks 18" Elm
1964 Witnesses, O.M. Elliot, PS # 2097, Book 46, P. 2; Stone.
S72W 68.2' 6" Elm

Continued on Back.

APPROVED

County Remonumentation
Peer Review Group

23 OCT 1998 NCC

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-9 Section Corner, Sections 23,24,25 & 26, T8N-R3E, New Haven Township

Found bent 1/2" re-rod with an unreadable cap, and 2 accessories from 1986 (E leg sign to SSE at 20.20', and CMP to SW at 24.90' [was unable to measure to CMP, under water]). Measured South 2637.01' (39.95 ch.) to K-10 (1822 GLO 40.00 ch., 1887 C.S. rec. 40.94 ch. [39.94 ch. corrected]), measured East 2605.97' (39.48 ch.) to L-9 (1822 GLO 39.88 ch.). The position of the bent 1/2" re-rod & unreadable cap is accepted as the best available evidence of the position of the original government corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-10 Section Corner, Sections 23,24,25 & 26, T8N-R3E, New Haven Township

Set a standard 20" Harrison monument at the position approved by the Shiawassee County peer review group.

- S02E 20.04' E-leg Arrow Sign
South 36.63' Found Nail & Tag # 24622 W Fc 14" Poplar
S45W 177.73' Set Nail & Tag # 39096 NW Fc P/P
S60E 158.95' Set Nail & Tag # 39096 N Fc 20" Willow
N45E 33.49' Set 1/2" Rod & Cap # 39096 in ditch bank
N40W 45.44' Stop Sign Post

(MONUMENT BOX INSTALLED IN NEW PAVEMENT 23 OCT 1998) NCC



Signed by John H. Rauser
Surveyor's Michigan License No. 39096

Date 10/21/98

A. Continued:

- 1973 Witnesses, J. F. Quine, PS # 10704, Book 17, P. 35; Drove 6" iron railroad spike flush with pavement aligned over and double distance from 1/8 Post and 1/4 Post to East.
- | | | |
|-------|-------|---|
| South | 20.3' | W leg of "Dead End" sign |
| South | 20.1' | E leg of "Dead End" sign |
| NW | 41.3' | Telephone cable marker |
| NW | 36.5' | Center of W end of 12" CMP road culvert |
| NE | 37.3' | Center of E end of same culvert |
| South | 4.4' | Center of sealcoat pavement |
- 1973 Survey, L. 1, P. 380, by John F. Quine, PS # 10704; Found iron stakes set by E. S. Brewer, Jr. 33' & 300' N. of 1/8 post in SW1/4 of Sec. 24. Establish 1/8 post from these, then extend line and double distance from 1/4 post to 1/8 post westerly to establish section corner. Measured 2605.5' between K-9 and L-9.
- | | | |
|-------|-------|-----------------------------------|
| NW | 41.3' | Aluminum telephone cable marker |
| NW | 36.5' | Center W end 12" CMP road culvert |
| NE | 37.3' | Center E end of same culvert |
| South | 20.3' | W leg of "Dead End" sign |
| South | 4.4' | Centerline of road |
- 1975 LCRC, L. 1, P. 534, by John F. Quine, PS # 10704; Reestablished at point indicated by extending line and doubling distance over 1/8 post & 1/4 post to East. Drove 6" iron railroad spike flush with sealcoat pavement. Measured 2605.50' between corners K-9 and L-9.
- | | | |
|-------|-----------|---|
| South | 20.3' | W leg of "Dead End" sign |
| South | 20.1' | E leg of "Dead End" sign |
| NW | 41.3' | Telephone cable marker |
| NW | 36.5' | Center of W end of 12" CMP road culvert |
| NE | 37.3' | Center of E end of same culvert |
| South | 4.4' | Center of sealcoat pavement |
| East | 1,302.75' | 1/8 Post |
| East | 2605.50' | 1/4 Post |
- 1986 Survey, L. 4, P. 483, by Mark L. VanRaemdonck, PS # 24622; Found R.R. Spike.
- | | | |
|------|--------|-------------------------|
| N50W | 37.80' | SE Fc road sign post |
| N55W | 40.97' | Top center Tel. cabinet |
| S20W | 24.90' | Top center 12" CMP |
| S02E | 20.20' | E leg arrow sign |
- 1995 Survey, L. 7, Pgs. 361-362, by Mark L. VanRaemdonck, PS # 24622; Found R.R. Spike; measured 2659.52' between corners K-9 and K-8, measured 2689.75' between corners K-9 and J-9.
- | | | |
|------|--------|-------------------------|
| N50W | 37.80' | SE Fc road sign post |
| N55W | 40.97' | Top center Tel. cabinet |
| S20W | 24.90' | Top center 12" CMP |
| S02E | 20.20' | E leg arrow sign |

SURVEY &
REMONUMENTATION

NOV 03 1998

SECTION

