

**SURVEY &  
MONUMENTATION**

APR 08 1996

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

<u>Shiawassee</u> (County)	Located In:	Corner Code #
		<u>K-11</u>
1. Public Land Survey	T 8 N R 3 E	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

RECORDED

95 SEP -5 PM 1:48

REGISTER OF DEEDS

*Spencer*  
SHIawassee COUNTY, MICH.

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Norman C. Caldwell, in a field survey on June 5, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

**K-11** Post placed by J. Wampler, 1822  
S73 1/2°E 12 lks. (7.92') 9" Beech  
S69°W 24 lks. (15.84') 18" Maple

Survey by L. Mason May 20-22, 1878, Recorded County Surveyors Records P 176-177, 198-199, 264.  
S2 1/4°E 255 lks. (148.5') 9" elm

Survey Road Book 4 Aug. 1916 P 44 (Vernon W. Royce) Large stone in crockery used.  
No witnesses.

L.C.R.C. by George F. Misjak L.S. 21271 Nov. 13, 1976.  
Recorded Dec. 8, 1978 L 2 P 30  
Fnd lg stone in crockery  
Replaced w/"T" bar 0.50' below bit. surface  
N25°E 109.4' SW cor. house  
N70°E 107.5' Flag pole  
N45°W 4.25' Railroad spike

Survey by Mark L. Vanraemdonck L.S. 24622 July 8, 1993,  
Recorded Aug 23, 1993. L 6 P 548  
Fnd T-iron  
N05°E 25.76' S. face road sign post  
N02°E 33.24' P.K. E. face tel. pole  
N70°E 55.68' Top cen. W end 12" Conc. culv.  
S30°W 40.27' P.K. E. face 10" maple

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

**K-11** Found record "T" iron as placed by ~~Mason~~ over L. Mason stone in crockery (1878). MISJAK

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**K-11** Section Corner 25,26,35,36 T8N,R3E

Fnd record "T" iron, 6" deep in asphalt road, 1' N of centerline and in line w/gravel Rd. centerline South  
Replaced w/Harrison marker and Mon. Box and is accepted as a careful and faithful perpetuation of the position of the original corner.

N75°E 167.42' 12018 tag in N. side P. pole  
N45°E 61.82' " " S. side 6" chinese elm  
N10°E 51.29' " " W. side 12" ash  
S70°W 136.60' " " N. side 12" maple  
N45°W 4.25' R.R. spike, no information on origin, not an acceptable position for Section Corner.

**APPROVED** 7/25/95

County Monumentation Peer Review Group M.L.V.

Signed by Norman C. Caldwell Date 5 JULY 1995

Surveyor's Michigan License No. 12018

**LIBER IR PG 104**