

LAND CORNER RECORDATION CERTIFICATE

APR 08 1996

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

95 SEP -5 PM 1:48

REGISTER OF DEEDS

*Kaye Shuckla*  
SHIAWASSEE COUNTY, MICH.

For corners in  
Shiawassee  
(County)

COMMISSION

Located In:

Corner Code #

- 1. Public Land Survey T 8 N R 3 E L-13  
T R  
T R  
T R
- 2. Property Controlling in Section S T R  
S T R  
S T R
- 3. Miscellaneous Property in Sec. S T R  
S T R

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Norman C. Caldwell, in a field survey on May 25, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-13 Post placed by J. Wampler, 1822  
S11°W 4 lks. (2.64') 30" Lymn  
N40°W 5 lks. (3.3') 5" Ironwood

Survey by L. Mason May 20-21, 1878, recorded County Surveyors record P 176-177  
N1°-25'W 60 1/2 lks. (39.9') 4" sugar

L.C.R.C. by Mark L. Vanraemdonck L.S. 24622 July 22, 1993  
Recorded Aug. 23, 1993 L 2 P 859

Fnd 12"x6"x5" stone with 12" dimension vertical. Fnd plow share on S side. Removed stone to search for remains of wood stake. Fnd. discolored soil but could not verify that it was the wood stake. Set rerod & cap #24622 in place of stone. Left plow share in place.

N10°E 38.91' top cen. E. end 36" cmp culv.  
N40°W 30.76' top cen. tele. cable box.  
N25°W 40.65' top cen. W. end 36" cmp culv.  
S88°-13'-01"W 2636.54' "T" iron at SW cor. section 36  
N88°-15'-20"E 2624.64' REI rerod & cap at SE cor. Section 36

J.F. Quine L.S. 10704 12/28/93 L 2 P 650  
Used record 1/2" bar per LX, p.859

6

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-13 Found record 1/2" bar w/24622 cap, plow point and stone alongside.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13 Standard South 1/4 Corner of Section 36, T8N-R3E  
Fnd. record 1/2" bar w/24622 cap, plow point and stone alongside. Replaced w/Harrison marker in centerline E-W gravel road, 15'E. of tree line S, and is accepted as a careful and faithful perpetuation of the position of the original corner.  
N10°E 39.08' top cen. E. end 36" c.m.p. culv.  
N25°W 40.65' " " W. end " " "  
S30°W 36.75' 1/2" bar w/10704 cap  
N40°W 30.76' top centerline tel. riser

APPROVED 7/25/95  
County Remonumentation M.L.V.  
Peer Review Group

Signed by *Norman C. Caldwell* Date 5 JULY 1995

Surveyor's Michigan License No. 12018