

SURVEY & REMONUMENTATION

NOV 03 1998

**1998 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

SECTION

For corners in

Shiawassee Located In: New Haven Twp Corner Code #

(County)



- 1. Public Land Survey T 8 N R 3 E M - 9
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John H. Rauser, P.S., in a field survey on February 20, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M - 9 Standard Corner, Sections 24 & 25, T8N-R3E, New Haven Township
 1822 Wood post placed by Joseph Wampler, D.S.
 Lynn 10 N09W 19 links
 R. Oak 16 S38E 16.5 links
- ???? Shiawassee Drain Records, Road Book 4, P. 53B; Found stone and old stake.
 N43 1/4W 43.8' 8" Maple
 N32 3/4E 57' 12" Maple

APPROVED
 County Remonumentation
 Peer Review Group
 23 OCT 98
 NCC

Continued on back:

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M - 9 Standard Corner, Sections 24 & 25, T8N-R3E, New Haven Township
 Found Pinched Pipe in Mon. Box, and 1 accessory from 1969 (Sign Post to SW at 42.5'), and 1 accessory from 1992 (CMP to NW at 42.36'). Measured West 2576.16' (39.03 ch.) to L-9 (1822 GLO 39.88 ch), measured South 2629.25' (39.84 ch.) to M-10 (1822 GLO 40.00 ch.), measured North 12.08' (18 links) to A-9, T8N-R4E (1822 GLO Jog = 21 links). We accept the position of the pinched pipe in a monument box as a careful and faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M - 9 Standard Corner, Sections 24 & 25, T8N-R3E, New Haven Township
 Set a standard 20" Harrison monument at the position approved by the Shiawassee County peer review group as a careful and faithful re-establishment of the position of the original corner.
- S55W 40.75' Chisld "+" top S end 24" CMP
- S60W 42.47' N edge Rd/Stop sign post
- N45W 55.98' E edge underground GTE marker post
- N43W 42.43' Chisld "+" top N end 24" CMP
- N45E 53.95' S edge Stop sign post
- N60E 162.66' Set nail & tag # 39096 S Fc P/P
- N05E 12.08' Found 1/2" re-rod, A-9 T8N-R4E



Signed by John H. Rauser
 Surveyor's Michigan License No. 39096

Date 10/21/98

A. Continued:

- 1916 Shiawassee Drain Records, Road Book 7, P. 36; Stone, no accessories.
- 1919 Shiawassee Drain Records, Road Book 28, P. 30; Found stone at corner.
N43 1/4W 43.8' 10" Maple
N32 3/4E 57' 15" Maple
- 1920 SCRC Records, Field Notes, Topo begins at M-9, no description of monument given.
- 1943 Shiawassee Drain Records, Butcher Drain Minutes of Survey, by E. S. Brewer, PS # 6515, surveyed centerline of drain is 1300' West of M-9, no description of monument given.
- 1964 Shiawassee Drain Records, Book 46, P. 2, by O. M. Elliot, PS # 2097; No description of the monument given.
N34°43W 43.8' 10" Maple
N32 3/4E 57' 15" Maple
- 1969 Shiawassee Drain Records, Field book 15, P. 123, by J. F. Quine, PS # 10704; Found 1" iron pipe stake 6" deep, bent to south.
NW 47.7' NE cor. of aluminum telephone cable marker sign on E side of telephone pole
SW 42.5' Stop sign post
SE 27.1' SW end of 12" CP culvert
NE 50.3' Stop sign post
- 1973-75 Survey & LCRC, L. 1, P. 550, L. 1, P. 535, by J. F. Quine, PS # 10704; Found 1" iron pipe stake 6" deep, bent to south.
NW 47.7' NE cor. of aluminum telephone cable marker sign on E side of telephone pole
SW 42.5' Stop sign post
SE 27.1' SW end of 12" CP culvert
NE 50.3' Stop sign post
- 1992 LCRC, L. 2, P. 825, by Norman C. Caldwell, PS # 12018; Fnd. 1" pipe bent, per L. 1, P. 535, pulled & reset 1" P. Pipe & Mon. Box.
N45E 54.56' S edge stop sign
S40W 48.12' W edge road sign
N05W 12.0' Iron rod NW cor. Sec. 30.
N45W 42.36' Chis. "1" in 24" CMP N end

SURVEY &
REMONUMENTATION

NOV 03 1998

SECTION



3007718
Page: 2 of 2
10/27/1998 03:22P