

**1998 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

SURVEY &
REMONUMENTATION

NOV 03 1998

For corners in

SECTION

Shiawassee
(County)

Located In: New Haven Twp Corner Code # _____



3007710
Page: 1 of 1
10/27/1998 03:22P

Kaye Grubba - Shiawassee Co. REMON

Lb-1 Pg-263

1. Public Land Survey T 8 N R 3 E M - 10
 T _____ R _____
 T _____ R _____
 T _____ R _____
 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
 5. Private Claims _____

County Remonumentation
Peer Review Group

23 OCT 98 NCC

I, John H. Rauser, P.S., in a field survey on April 27, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | 5 | | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

M - 10 Standard 1/4 Corner, Section 25, T8N-R3E, New Haven Township

- 1822 Wood post placed by Joseph Wampler, D.S., Lynn 20 S65E 14 links
Lynn 16 N18W 25 links
- 1876 Survey by Lyman Mason shows M-10 to be South of A-10, T8N-R4E, Hazelton Twp a distance of 28 links (18.48').
- 1943 Shiawassee Drain Records, Butcher Drain Minutes of Survey, by E. S. Brewer, PS # 6515, surveyed centerline of drain is 1312' West of M-10, no description of monument given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M - 10 Standard 1/4 Corner, Section 25, T8N-R3E, New Haven Township

Found stone and wood fibers along side N edge of stone, 1.7' below gravel surface in original soil, held position of source of wood fibers. The area this corner is located consists largely of undivided farmland. Very little survey work appears to have been done here. Geek Road was paved during the early 1970's, and now appears to be made up of almost nothing but "cold patches". There is an apparent occupied farm field line to the West of the approximate corner location. The portion of Geek Rd at the approximate corner location is in good shape. There was no evidence of anyone ever digging for the corner since the road was paved. There is an occupied field line to the East 1 rod to the North at the approximate location of A-10, T8N-R4E, which also did not appear to be monumented. In 1910 V. W. Royce, C.S. found a "badly decayed stake" and set a drag tooth and axe at A-10, T8N-R4E, to perpetuate the position. Upon excavation of the approximate location of A-10, we recovered the drag tooth along side of a stone, 1.5' below the road surface. Using field measurements, calculated a possible position of M-10 to excavate. Meanwhile Geek Rd had been milled and all asphalt removed in preparation for resurfacing. This fortunate timing allowed a perfect opportunity to excavate a "really nice sized hole". Upon excavation we recovered a large stone with wood fibers along side the N edge of the stone. This position fit the occupied field line to the West, and matched the 1876 County Surveyor's jog measurement of 28 links (18.48') South of A-10. Measured North 2629.25' (39.84 ch.) to K-9 (1822 GLO 40.00 ch), measured South 2617.71' (39.66 ch.) to K-11 (1822 GLO 40.00 ch.), measured West 2596.40' (39.34 ch.). We accept the position of the wood fibers along the North edge of a stone as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M - 10 Standard 1/4 Corner, Section 25, T8N-R3E, New Haven Township

Set a standard 20" Harrison monument at the position approved by the Shiawassee County peer review group

- West 60.94' & 37.78' Set 1/2" re-rods & caps # 39096 in line with corner
- S50W 24.85' Set chisld "v" notch N end 12" conc. culv.
- N65W 25.19' Set chisld "v" notch S end 12" conc. culv.
- N80E 137.88' Set PK & tag # 69096 S Fc P/P
- North 18.48' Found drag tooth along side stone, raised with 1/2" re-rod & cap # 39096, A-10, T8N-R4E

Signed by John H. Rauser
 Surveyor's Michigan License No. 39096

Date: 10/27/98

