

SECTION

1999 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Shiawassee  
(County)

Located In:  
Hazelton Twp

Corner Code #



3026111  
Page: 1 of 1  
10/05/1999 02:19P  
L-1 P-304

- 1. Public Land Survey T8N R4E M-8
- 2. Property Controlling in Section S T R
- 3. Miscellaneous Property in Sec. S T R
- 4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

**APPROVED**  
County Remonumentation  
Peer Review Group  
1 OCT 99  
ALC

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John H. Rauser, P.S., in a field survey on September 13 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

**M-8** Standard 1/4 Corner, Section 24, T8N-R4E, Hazelton Township, Shiawassee County  
1822 Wood post placed by J. Wampler, D.S., Elm 18" N20E 37lks (24.42')  
Lynn 7" S16W 27lks (17.82')

1993 Act 132 by M.L. Vanraemdonck, P.S. 24622, L. 6, P. 485, calculated the position of M-8, 2643.14' North of M-9, no witnesses or explanation of the position as shown.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

**M-8** Standard 1/4 Corner, Section 24, T8N-R4E, Hazelton Township, Shiawassee County  
Found no evidence of original government accessories. Found no object at the position of M-8, milling and overlay has been placed on M-13 at this position. Calculated the position of M-8 mid-way and on line between M-9 and M-7, as recovered in the field. Measured distance between M-9 and M-7 = 5285.98, mid-way calculates to be 2642.99'. This position measures 0.15' less than the position from the 1993 record, which is assumed to be set at the same single proportionate measure. The angle measured from M-9, M-8 to L-8 = 90°20'17", 1993 record = 90°20'03". The occupation to the West at this position is a tree row, the center line of which was tied in the field and is located 5'± South of the calculated position. A fence occupation to the East is 281.4' ± N of this position, the mean closing jog using the M-9, A-9 jog of 250.60 and the M-7, A-7 jog of 308.22' calculates to be 279.41'. We located, as closely as possible, the path of the original drain before it was re-located for the M-13 crossing. GLO call for drain = 1841.4' (27.90 chains) we measured 1810'± to apparent old crossing. The drain has been relocated for the crossing of State Highway M-13 and cannot be considered a reliable accessory. We recommend accepting the calculated position as the a careful and faithful re-establishment of the lost corner M-8 by single proportionate measure and place a 1/2" re-rod under a 5/8" re-rod welded to a standard Shiawassee County Harrison monument removable top and a custom 3" tall monument box which is bolted into the concrete pavement below the asphalt overlay.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**M-8** Standard 1/4 Corner, Section 24, T8N-R4E, Hazelton Township, Shiawassee County  
Set a 1/2" re-rod under a 5/8" re-rod welded to a standard Shiawassee County Harrison monument removable top and a custom 5" tall monument box which is bolted into the concrete pavement below the asphalt overlay at the position approved by the Shiawassee County Peer Review Group.

- N55E 68.41' Set spike w/tag #39096 in S face 8" Elm
- S56E 63.46' Set spike w/tag #39096 in SW face 10" Elm
- N88W 53.25' Set spike w/tag #39096 in S face 10" Oak
- N26W 91.24' Set spike w/tag #39096 in E face 8" Elm

Signed by John H. Rauser  
Surveyor's Michigan License No. 39096

