

LAND CORNER RECORDATION CERTIFICATE
2000 Remonumentation Program
Filing Requirement of Act 74, Mich. P.A. 1970

JAN 16 2001

SECTION

For corners in

SHIAWASSEE
(County)

Located In: Hazleton Twp.
Corner Code



3044420
Page: 1 of 1
12/04/2000 09:53A
L-1 P-360

Kaye Grubba - Shiawassee Co. REMON

- 1. Public Land Survey T 8N R 4E C-13
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____
- 3. Miscellaneous Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____

Register of Deeds Stamp & File Number

APPROVED
NOV 27 2000
County Remonumentation

Peer Review Group **B C D E F G H I J K L M**

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, John H. Rauser, P.S., in a field survey on August 20 00 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

2	6	5	4	3	2	1
3						
4	7	8	9	10	11	12
5						
6	18	17	16	15	14	13
7						
8	19	20	21	22	23	24
9						
10	30	29	28	27	26	25
11						
12	31	32	33	34	35	36
13						

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- C-13 Standard Section Corner, Sections 31 & 32, T8N-R4E, Hazelton Township, Shiawassee County
1822 GLO wood post set by J. Wampler, D.S., witnessed by, N21E 12 lks (7.92') 10" Ash, S65W 26 lks (17.16') 8" Ash
1851 County Survey by Monroe Holly, D.S.; no witnesses listed, B-1 to C-1 = 40 ch (2640'), B-1 to A-1 = 53.85 ch (3554.1'), Book "B", P.23.
1874 County Survey by Lyman Mason, C.S., witnessed by S35-1/4E 81.5lks (53.79') 14" S. Maple, S61E 82.25lks (54.29') 12" S. Maple
1877 County Survey by Lyman Mason, C.S., witnessed by N20°35'E 111lks (73.26') 8" Hickory.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-13 Standard Section Corner, Sections 31 & 32, T8N-R4E, Hazelton Township, Shiawassee County
Found no evidence of the original government accessories. Found 32" Hickory tree in the location as described in the 1877 Mason record. Established the position for excavation based on record witness to Hickory tree. Place a PK nail using a corrected compass bearing and measuring 73.3' from an axe scar in the West face of the Hickory. Excavated below road gravel into original soil approximately 3 feet and found wood post between two rocks, approximately 0.12 feet East and 0.15 feet North of the set PK position. Measured West to B-13, 2630.73 feet, 1877 Mason 2630.43 feet. Occupied fence line to North at the 1/8 line fits the split dimension, B-13 to occ. = 1315.64 feet; C-13 to occ. = 1315.12 feet, as established from fence ties. We recommend that the found wood post be accepted as a careful and faithful perpetuation of the original government corner and that it be replaced with a standard Shiawassee County Harrison monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-13 Standard Section Corner, Sections 31 & 32, T8N-R4E, Hazelton Township, Shiawassee County
Set standard Shiawassee County Harrison monument over the wood post, left the rocks and wood post in place.
N20E 73.07' Set N&T #39096 in old blaze of 30" Hickory
N70W 92.91' Set N&T #39096 in SE root of 54" Oak
N65E 51.19' Set chiseled "x" on top North end of 21" culvert
S65W 28.37' Set chiseled "x" on top South end of 21" culvert
West 11.93' C-1, T7N-R4E

Signed by John H. Rauser
Surveyor's Michigan License No. 39096



Date 11/09/00