

SURVEY & REMONUMENTATION

COPY

FEB 08 2001

SECTION

2000 REMONUMENTATION PROGRAM RECEIVED FOR RECORD
LAND CORNER RECORDATION CERTIFICATE NO. PAGE NO.
Filing Requirement of Act 74, FILE NO. #122 Arbela
Mich. P.A. 1970

For corners in: ARBELA TWP.

- Tuscola Located In: Corner Code #
1. Public Land Survey T 10N R 7E K-1
2. Property Controlling S T R
3. Miscellaneous S T R
Property in Sec. S T R

00 DEC 19 PM 1:37

TUSCOLA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

I, Kari M. Lohela, in a field survey on August 29, 20 00 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 1-13. A dot is present in cell K-1.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1821 G.L.O. NOTES, JOSEPH WAMPLER, D.S., INT. T.L. 1.15 EAST OF POST TO SEC. 35 & 36, BEECH 20 S 62 W 21, BEECH 10 N 79 E 10

FOUND NO RECORDS OF SUBSEQUENT RESTORATION OF CORNER K-1

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" PIPE 2.03' SOUTH OF STD. TOWNSHIP LINE.

EXTENDED SECTION LINE NORTHERLY, FROM CORNER K-2 AND FOUND 1" PIPE, TO INTERSECTION WITH STD. TOWNSHIP LINE. SET AMENDED CORNER ON STD. TOWNSHIP LINE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 36" CONCRETE MONUMENT WITH STANDARD BRASS CAP STAMPED K-1 AC (AMENDED CORNER), T10N-R7E, IN MONUMENT BOX.
N 60° E, 132.42' SET REMON. TAG & NAIL ABOVE FOUND SCREW IN NW FACE OF UTILITY POLE
S 65° E, 126.44' SET REMON. TAG & NAIL IN SW FACE OF UTILITY POLE
SOUTH, 2.03' FOUND 1" PIPE
WEST, 76.76' FOUND TUSCOLA COUNTY MOUNUMENT STAMPED K-13, T11N, R7E
N 35° W, 60.94' SET REMON. TAG & NAIL IN SW FACE OF 18" ASH

Signed by

Kari M. Lohela

Date 12/18/00

Surveyor's Michigan License No. 44289



APPROVED BY TUSCOLA COUNTY REMONUMENTATION PEER GROUP 12/06/2000

156 MW RRL

