

**SURVEY &
REMONUMENTATION**

COPY

FEB 08 2001

**2000 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74,
Mich. P.A. 1970**

SECTION

For corners in: ARBELA TWP.

Tuscola Located In: Corner Code #
(County)

1. Public Land Survey T 10N R 7E K-3
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat
5. Private Claims

I, Kari M. Lohela, in a field survey on August 29, 20 00 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1822 G.L.O. NOTES, JOSEPH FLETCHER, D.S., SET CORNER POST TO SECTIONS 1-2-11&12, BEECH 12 S 54 E 8, BEECH 10 S 47 W 11
- AUG. 24, 1971, SURVEY L.1 P.164, ROBERT KAY, PS 14096, FOUND 1/2" IRON, N 30 W 35.95' 30" MAPLE, S 45 W 50.70' TP, S 35 E 58.80' TP
- FEB 16, 1972, SURVEY L.1 P.440, ROBERT KAY, PS 14096, SAME OBJECT AND ACCESSORIES AS SURVEY L.1 P.164
- NOV. 19, 1976, SURVEY L.467 P.803, DAVID ROWE, PS 11192, FOUND 1/2" RE-ROD, N 50 E 38.35' PK 30" MAPLE, N 55 W 75.15' PK IN P.P., S 35 E 61.70' PK IN T.P., S 30 W 97.87' PK IN P.P.
- DEC. 30, 1976, LCRC, P.56 ARBELA TWP., KENNETH DUNTON, PS 23503, FOUND 1/2" RE-ROD, N 50 E 38.35' PK IN 30" MAPLE, N 55 W 75.15' PK IN P.P., S 30 W 97.87' PK IN P.P.
- MAY 29, 1985, SURVEY L.550 P.1127, ROBERT KAY, PS 14096, FOUND 1/2" IRON, S 45 W 50.70' NAIL IN T.P., N 45 W 45.05' TOP CENTER TELE. RISER BOX, S 35 E 51.70' PK NAIL IN T.P.
- JULY 26, 1991, SURVEY L.646 P.389, A.F. MILLER, PS 12024, FOUND RE-ROD, N 45 W 44.97' CENTER TELE. PED., S 40 E 62.47' CENTER TELE. PED., S 50 W 48.80' CENTER TELE. PED., S 45 W 44.53' CENTER TELE. PED.
- APRIL 6, 1999, SURVEY L.767 P.1445, LIONEL EMERY, PS 24593, FOUND 1/2" IRON, S 40 E 76.97' SET NAIL SW FACE 18" WHITE PINE, S 60 W 50.81' FOUND NAIL & WASHER IN UTILITY POLE, S 30 W 97.87' FOUND PK NAIL IN P.P., N 55 W 76.13' SET NAIL IN NE FACE OF NEW P.P.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND 1/2" REBAR. RECOVERED 7 ACCESSORIES WHICH INDICATE THAT 1/2" REBAR IS IN SAME POSITION AS SURVEYS AND LCRC CITED ABOVE.

ACCEPTED FOUND 1/2" REBAR AS BEST AVAILABLE EVIDENCE OF ORIGINAL CORNER POSITION.

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. _____
FILE NO. *119 Arbela
00 DEC 19 PH 1:36
Gregory M. Schuen
TUSCOLA COUNTY
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6			5		4		3		2		1
3												
4	7			8		9		10		11		12
5												
6	18			17		16		15		14		13
7												
8	19			20		21		22		23		24
9												
10	30			29		28		27		26		25
11												
12	31			32		33		34		35		36
13												

