

SURVEY & REMONUMENTATION

COPY

FFR 08 2001

**2000 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74,
Mich. P.A. 1970**

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. _____
FILE NO. **#115 Arbela**

00 DEC 19 PH 1:35

Arnel M. Mendenhall
TUSCOLA COUNTY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in: ARBELA TWP

Tuscola Located In: Corner Code #
(County)

- 1. Public Land Survey T 10N R 7E K-6
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat

5. Private Claims

I, Kari M. Lohela, in a field survey on August 29, 20 00 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6			5			4			3		1
3												
4	7								10	11		12
5												
6	18			17			16			15	14	13
7												
8	19			20			21			22	23	24
9												
10	30			29			28			27	26	25
11												
12	31			32			33			34	35	36
13												

A. Description of original monument and accessories and/or subsequent restoration:

1822 G.L.O. NOTES, JOSEPH FLETCHER, D.S., SET ¼ CORNER POST, BEECH 12 S 24 W 12, BEECH 20 N 87 E 19

AUG. 22, 1888, JOHN TESKEY, SURVEYOR, STAKE AND CROCKERY, BEECH 10 N 76 W 15

APRIL 20, 1972, LCRC P.16, ARBELA TWP., GERALD MCKELVEY, PS 19001, FOUND ½" RE-ROD AT EXTENSION OF OCCUPATION LINE OF WEST SECTION LINE, SW 29.90' SURVEYOR'S DISK IN UTILITY POLE, NE 28.23' X IN CENTER OF BOULDER, SW 23.05' SURVEYOR'S DISK IN FENCE POST

JULY 7, 1974, SURVEY L.444 P.196, ROBERT KAY, PS 14096, NO MENTION OF OBJECT FOUND OR SET, N 45 E 26.43' SW POINT ON BIG STONE, S 80 W 29.65' E. FACE T.P., S 50 W 130.20' NE CORNER HOUSE FOUNDATION

JUNE 20, 1979, SURVEY L.498 P.235, KENNETH DUNTON, PS 23503, FOUND ½" ROD, S 85 W 29.84' RLS TAG IN T.P., S 68W 68.85' PK IN P.P., S 80 E 69.17' PK IN T.P.

SEPT. 1, 1982 LCRC P.70, ARBELA TWP., KENNETH DUNTON, PS 23503, SAME OBJECT AND ACCESSORIES AS IN SURVEY L.498 P.235

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND ½" REBAR ON EXTENSION OF OCCUPIED LINES TO EAST AND WEST. RECOVERED 3 ACCESSORIES WHICH INDICATE THAT ½" REBAR IS IN SAME POSITION AS 1982 LCRC, 1979 AND 1974 SURVEYS CITED ABOVE.

ACCEPTED ½" REBAR AS BEST AVAILABLE EVIDENCE OF ORIGINAL CORNER POSITION.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REMOVED ½" REBAR AND SET 36" CONCRETE MONUMENT WITH STANDARD BRASS CAP STAMPED K-2, T10N-R7E, IN MONUMENT BOX.

N 40° E, 28.61' SET ½" REBAR

S 65° E, 69.04' SET REMON. TAG & NAIL ABOVE PK NAIL IN SW FACE OF UTILITY POLE

S 42° W, 137.09' NE CORNER OF CONC. PORCH, HOUSE #8750

S 74° W, 68.83' SET REMON. TAG & NAIL ABOVE PK NAIL IN N FACE OF UTILITY POLE

SURVEY & REMONUMENTATION

FEB 08 2001

K-6 T10N-R7E

SECTION

Signed by

Kari M. Loehla

Date 12/18/00

Surveyor's Michigan License No. 44289



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975

REVISED JAN., 1983

REVISED OCT., 1995

APPROVED BY TUSCOLA COUNTY
REMONUMENTATION PEER GROUP

12/06/2000

1500
MWP
N 213

