

1999
 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Arbela Twp.

<u>Tuscola</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>10</u> N <u>R7E</u>	<u>K-9</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

RECEIVED FOR RECORD
 INDEX NO. _____ PAGE NO. _____
 FILE NO. #116
ARBELA TWP
 99 DEC -7 PM 3:37
 TUSCOLA COUNTY
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Kenneth D. Dunton, in a field survey on Aug. 14, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey Instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

June, 1822, Joseph Fletcher, D.S. Set corner Sections 23, 24, 25 & 26, T10N-R7E, Beech 9" S31°E 15 links, W. Ash 6" N1°W 12 links. Sept. 21, 1886 John A. Teskey, Co. Surveyor, survey of Sec. 23, stake established at corner, stone & crockery at corner, W. Oak 2" S76 1/2°W 1.08 links. Oct. 28, 1886, John A. Teskey, Co. Surveyor, survey of NW 1/4 Sec. 24, no mention of object found or set or accessories. Jan. 25, 1973 Survey L-443, P-381 by Carl H. Carlson, P.S. #9189, found nail, S41°W 62.77' P. Pole, N46°E 55.98' P. Pole, S43°E 61.34' P. Pole. March 14, 1973 Survey L-443, P-383 by Carl H. Carlson, P.S. #9189, found nail, S35°W 60.1' P. Pole, S42°33'E 59.0' P. Pole, N41°17'E 58.3' P. Pole. Nov. 21, 1974 Survey L-451, P-150 & 151 by David T. Rowe, P.S. #11192, found nail, S40°W 62.49' R.L.S. 11192 tag in P. Pole,

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: Sec. A con't on back of form

1999 K-9 Found 1/2" iron rod in monument box. Accepted 1/2" rod as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-9 Removed 1/2" iron rod and perpetuated with 3/4" pipe and 5/8" iron rod with standard brass cap stamped K-9, T10N-R7E. Encased pipe, rod & cap in concrete in monument box.
 N52°W 31.86' found 1/2" iron rod & cap #37276.
 N33°E 38.40' found 1/2" iron rod & cap #37276.
 S54°E 48.80' found 1/2" iron rod & cap #37276.
 S45°E 47.42' found 1/2" iron rod.
 S18°W 57.4' conc. F.A.S. marker (leaning).
 S34°W 63.05' fnd. P.K. nail & tag #37276 in SE face P. Pole.

Signed by [Signature]
 Surveyor's Michigan License No. 23503

Date 12-1-99

APPROVED
 12-1-1999

[Signature]
 RLB



