

COPY

1999
REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Arbela Twp.

<u>Tuscola</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T10N R7E	K-11
2. Property Controlling in Section	S T R	
3. Miscellaneous Property in Sec.	S T R	

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. _____
MEMO #107
ARBELA TWP.
99 DEC -7 PM 3:37
TUSCOLA COUNTY
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kenneth D. Dunton, in a field survey on July 18, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

June, 1822, Joseph Fletcher, D.S. Set corner to Secs. 25, 26, 35 & 36, T10N-R7E, Beech 14" S39°W 36 links, Beech 9" N44°W 22 links. Aug. 27, 1888 Survey of Sec. 36 by John A. Teskey, Co. Surveyor, stake established at corner, W. Oak 3" S52°E 57 1/2 links, Hickory 3" S33°E 65 links. Aug. 30, 1888 Survey of Southeast 1/4 Sec. 35 by John A. Teskey, Co. Surveyor, no mention of object found or set or accessories. April 11, 1973 L.C.R.C. Page 26 by David T. Rowe, P.S. #11192, fnd. P.K. nail, S50°W 45.07' nail in T. Pole, N45°W 112.19' nail in P. Pole, N55°E 52.59' nail in 18" tree. June 17, 1974 L.C.R.C. Page 65 by Bernard Griggs, Jr. P.S. #14763, found nail in intersection of Belsay and Arbela Roads, the nail was left in place with following witnesses:

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1999 K-11 Found 1/2" iron rod & cap #11192 in monument box. Accepted 1/2" rod & cap as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-11 Drove rod & cap down & placed 3/4" pipe over 1/2" rod, placed 5/8" iron rod & standard brass cap over 3/4" pipe. Brass cap stamped K-11, T10N-R7E. Encased rod, pipe & cap in concrete in monument box.
S49°W 45.35' fnd. nail & tag #32332 in NW face T. Pole stub.
N49°E 53.12' fnd. nail & tag #32332 in SE face 34" Poplar.
S51°E 50.25' fnd. nail & tag #32332 in SW face T. Pole stub.
N53°W 112.71' set spike & remon. tag in NE face P. Pole (fnd. nail in SE face).

Signed By [Signature]
Surveyor's Michigan License No. 23503

Date 12-1-1999

APPROVED
12-1-1999
[Signatures]



