

1999  
 REMONUMENTATION PROGRAM  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

**COPY**

For corners in Arbela Township

<u>Tuscola</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T10NR 7E</u>	<u>K-12</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

RECEIVED FOR RECORD  
 USER NO. \_\_\_\_\_ PAGE NO. \_\_\_\_\_  
 FILE NO. #116  
ALBELA Twp.  
99 DEC -7 PM 3:37  
 TUSCOLA COUNTY  
 REGISTERED OFFICES

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Kenneth D. Dunton, in a field survey on July 18, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

June 1822 Joseph Fletcher, D.S. Set 1/4 corner to Secs. 35 & 36, T10N-R7E, Pine 8" S60°E 6 links, B. Ash 9" N40°E 16 links. August 27, 1888 Survey of Sec. 36 by John A. Teskey, Co. Surveyor, proportional distances, Pine stump 12" N76 1/4°E 30 3/4 links, stone 18 x 6 x 10 at corner. August 30, 1888 Survey of SE 1/4 Sec. 35 by John A. Teskey, Co. Surveyor, see notes of Sec. 36. April 1975 L.C.R.C. Page 48A by James A. Beck, P.S. #21559, found "T" iron, East 32.93' "T" iron at property corner, East 35.00' R.L.S. 11192 tag in T. Pole, N65°W 54.16' R.L.S. 11192 tag in T. Pole. Jan. 21, 1988 Survey L-579, P-1008 & 1009 by Kenneth D. Dunton, P.S. #23503, no mention of object found or set or accessories.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: Sec. A con't on back of form.

1999 K-12 Found "T" iron in monument box. Accepted the "T" iron as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-12 Removed "T" iron and perpetuated with 3/4" pipe and 5/8" iron rod & stamped brass cap. Stamped brass cap K-12, T10N-R7E. Encased pipe, rod & cap in concrete in monument box.  
 S29°W 54.00' fnd. notch chiseled atop S. end 12" CSP D/W culvert.  
 S86°E 26.23' chiseled notch atop N. end 12" CSP D/W culvert.  
 S31°W 26.10' fnd. P.K. nail & tag #37276 in NE cor. 4" x 4" wood mailbox post.  
 West 9.78' fnd. 1/2" iron rod at W. edge pavement.  
 N33°E 49.82' fnd. rivet atop S. end 12" CSP D/W culvert.  
 East 1.3' physical centerline N-S pavement.

Signed by [Signature]  
 Surveyor's Michigan License No. 23503

Date 12-1-1999

APPROVED  
 12-1-1999

[Signature]  
 RLB



