

SURVEY & REMONUMENTATION

FEB 08 2001

COPY

SECTION

**2000 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74,
Mich. P.A. 1970

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. _____
FILE NO. **#117 Arbela**

00 DEC 19 PM 1:36

Anna M. Moberg
TUSCOLA COUNTY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in: ARBELA TWP.

Tuscola Located In:
(County)

Corner Code #

- 1. Public Land Survey T 10N R 7E L-5
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R
 in Section S _____ T _____ R
- 3. Miscellaneous S _____ T _____ R
 Property in Sec. S _____ T _____ R

4. Lot No. _____, Recorded Plat

5. Private Claims

I, Kari M. Lohela, in a field survey on August 29, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

1822 G.L.O. NOTES, JOSEPH FLETCHER, D.S., SET ¼ CORNER POST, BIRCH 16 S 47 E 16, ASH 9 N 19 E 27

AUG 22, 1888, JOHN TESKEY, SURVEYOR, STAKE ESTABLISHED AT CORNER, BEECH 12 S 24 W 12

APRIL 19, 1971, SURVEY L.1 P.2, DAVID ROWE, PS 11192, NO MENTION OF OBJECT FOUND OR SET, N 5 E 52.8' P.P., SOUTH 34.8' FENCE POST

AUG.15, 1971, LCRC P.13, ARBELA TWP., DAVID ROWE, PS 11192, FOUND RE-ROD, NORTH 33.0' PROPERTY CORNER, SOUTH 34.8' FENCE CORNER POST, N 05 E 52.8' P.P., SOUTH 2.7' CENTERLINE ASPH.

APRIL 24, 1972, LCRC P.14, ARBELA TWP., GERALD MCKELVEY, PS 19001, FOUND ½" RE-ROD AT CENTERLINE OF MILLINGTON ROAD AT EXTENSION OF OCCUPATON LINE, NE 53.50' SURVEYOR'S DISK IN UTILITY POLE, SOUTH 34.92' SURVEYOR'S DISK IN FENCE POST, SE 49.35' SURVEYOR'S DISK IN MAIL BOX POST

JULY 27, 1972, SURVEY L.2 P.37, DAVID ROWE, PS 11192, OBJECT AND ACCESSORIES SAME AS IN LCRC P.13, ARBELA TWP.

SEPT. 23, 1972, SURVEY L.2 P.105, DAVID ROWE, 11192, OBJECT AND ACCESSORIES SAME AS IN SURVEY L.1. P.2

NOV. 19, 1974, SURVEY L.453 P.496, DAVID ROWE, PS 11192, NO MENTION OF OBJECT OR ACCESSORIES

APRIL 16, 1975, SURVEY L.452 P.643, JAMES BECK, PS 21559, OBJECT AND ACCESSORIES SAME AS LCRC P.13, ARBELA TWP.

APRIL 9, 1984, SURVEY L.542 P.391, WILLIAM WINIARSKI, PS 23857, OBJECT AND ACCESSORIES SAME AS IN LCRC P.13, ARBELA TWP.

NOV. 19, 1992, SURVEY L.636 P.884, JONATHAN FIELD, PS 37276, FOUND ½" ROD, NORTH 33.0' PROPERTY CORNER, N 05 E 52.80' P.P., S 60 E 51.16' TOP CENTER E. END 15" CMP, N 45 E 31.36' TOP CENTER W. END 15" CMP, SOUTH 1.7' CENTERLINE ASPH. ROAD, S 65 E 45.70' CENTER MAILBOX POST

L-5 T10N-R7E

APRIL 11, 1996, SURVEY L.731 P.678, EARL GRAVLIN, PS 23510, OBJECT AND ACCESSORIES SAME AS IN LCRC P.13, ARBELA TWP.

JU 22, 1999, SURVEY L.789 P. 885-886, JONATHAN FIELD, PS 37276, FOUND 1/2" ROD IN MON. BOX, SOUTH 49.88' 1/2" ROD, S 45 E 51.16' NOTCH IN W. END 24" CMP, N 20 E 53.25' NAIL & TAG #40162 IN W FACE P.P., N 40 E 31.42' NOTCH IN W. END 18" CMP

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" REBAR IN MONUMENT BOX ON EXTENSION OF OCCUPIED LINES TO NORTH AND SOUTH. RECOVERED 5 ACCESSORIES WHICH INDICATE THAT 1/2" REBAR IS IN SAME POSITION AS SURVEYS AND LCRC'S CITED ABOVE.

ACCEPTED FOUND 1/2" REBAR AS BEST AVAILABLE EVIDENCE OF ORIGINAL CORNER POSITION.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

PLACED STANDARD BRASS CAP STAMPED L-5, T10N-R7E, OVER 1/2" BAR. ENCASED CAP AND BAR IN CONCRETE IN EXISTING MONUMENT BOX.

NORTH, 32.91' FOUND 1/2" REBAR

N 12° E, 53.26' SET REMON. TAG & NAIL ABOVE FOUND #40162 TAG IN SW FACE OF UTILITY POLE

S 10° E, 31.88' FOUND NOTCH IN CROWN AT W. END OF 15" CMP CULVERT

S 45° W, 51.18' FOUND NOTCH IN CROWN AT E. END OF 15" CMP CULVERT

Signed by

Kari M. Loehla

Date
12/18/00

**APPROVED BY TUSCOLA COUNTY
REMONUMENTATION PEER GROUP**

*1500
MWP
RL13*

12/06/2000

surveyor's Michigan License No. 44289



SECTION

FEB 08 2001

SURVEY &
REMONUMENTATION

