

1999
REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Arbela Twp.

<u>Tuscola</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T10N R7E</u>	<u>L-7</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

COPY

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. _____
FILE NO. #114
ARBELA TWP.
99 DEC -7 PM 3:38
TUSCOLA COUNTY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Kenneth D. Dunton, in a field survey on Aug. 7, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

June 1822, Joseph Fletcher, D.S. Set 1/4 section corner, Beech 20" N81°E 19 links, Pine 36" N4°E 9 links. Oct. 28, 1886 John A. Teskey, Co. Surveyor, survey of Sec. 24, stake from bearing trees. Aug. 22, 1888 John A. Teskey, Co. Surveyor, survey of Sec. 13, stake from bearing trees. July 31, 1969 recorded plat by Robert G. Kay, P.S. #14096. Plat of Candice Subd. L-3 of Plats, Pages 43 & 44. No mention of object found or set. April 20, 1972 L.C.R.C. Liber 1, Page 14 Arbela Twp., by Gerald R. McKelvey, P.S. #19001. Set 3/4" pipe from recorded plat of Candice Subd., South 24.13' surveyor's disk in utility pole, Southeast 65.68' surveyor's disk in 18" stump, North 32.27' surveyor's disk in fence post.

Section A con't on back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


1999 L-7 Found 3/4" x 18" iron pipe. Accepted the pipe as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-7 Removed 3/4" pipe & perpetuated with standard monument with brass cap stamped L-7, T10N-R7E. Placed monument box over monument.
N00°15'W 39.82' fnd. 1/2" iron rod in 4" sq. conc. mon. (bent & broken).
N00°36'E 80.15' set remon. tag & spike in E. face P. Pole.
N28°E 85.30' center 8" Maple.
N67°E 57.68' fnd. notch chiseled atop W. end 12" C.S.P. D/W culvert.
South 32.95' fnd. nail & 11192 tag in N. face R.R. tie gate post.
S40°W 41.75' fnd. nail & 11192 tag in N. face R.R. tie gate post.
S01°W 89.35' fnd. nail & 11192 tag in E. face P. Pole.
South 3'± E-W physical centerline bit. pavement.

Signed by [Signature]
Surveyor's Michigan License No. 23503

Date 12-3-1999



APPROVED
12-3-1999

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 20, 1971
REVISED MAY 14, 1975
REVISION REVISÉ JAN. 1983
REVISED OCT., 1995

