

1999
REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COPY

For corners in Arbela Twp.

<u>Tuscola</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T10N R7E	L-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. _____
FILE NO. #111
ARBELA TWP.
99 DEC -7 PM 3:37
TUSCOLA COUNTY
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kenneth D. Dunton, in a field survey on Aug. 14, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

June, 1822, Joseph Fletcher, D.S. Set 1/4 section corner between Secs. 24 & 25, T10N-R7E, Beech 9" S46°E 4 links, Elm 12" S30°W 26 links. Oct. 28, 1886, John A. Teskey, Co. Surveyor, survey of Sec. 24, stake established at corner, Elm 6" S 4 1/2°E 50 links, Maple 1" N 4 1/2°W 36 1/4 links. Aug. 23 & Oct. 1, 1972 L.C.R.C. Page 22 by David T. Rowe, P.S. #11192, found 1" iron bar, N02°W 54.17' nail in P. Pole, S45°E 55.37' nail in T. Pole, N08°W 103.53' SE corner house #6270. Sept. 18, 1972 Survey L-2, P-109 & 110 by David T. Rowe, P.S. #11192, found 1" iron bar, accessories same as L.C.R.C. Page 22 noted above. Mar. 14, 1973 Survey L-443, P-383 by Carl H. Carlson, P.S. #9189, found iron, N01°58'W 54.2' P. Pole, S54°32'E 55.4' P. Pole.

Sec. A con't on back of form

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1999 L-9 Found 1" iron bar in monument box. Accepted the 1" iron as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-9 Removed 1" iron bar & perpetuated with 3/4" iron pipe & 5/8" iron rod with standard brass cap stamped L-9, T10N-R7E. Encased pipe, rod & cap in concrete in monument box.
N13°W 103.55' SE corner footing at house #6270.
S39°W 60.03' fnd. tag # 22442 & nail in NE face 10" Pine.
S02°W 37.08' fnd. tag # 22442 & nail atop wood corner post.
N02°W 16.28' set 1/2" x 18" iron rod & cap #23503.
South 14.67' set 1/2" x 18" iron rod & cap #23503.

Signed by [Signature]
Surveyor's Michigan License No. 23503

Date 12-1-1999



APPROVED
12-1-1999
[Signatures]

Section A Con't.

June 18, 1976 Survey L-461, P-698 & 699 by David T Rowe, P.S. #11192, iron 1" sq., accessories same as L-443, P-383.

