

**SURVEY &  
REMONUMENTATION**

APR 25 1995

**COMMISSION**

1994 REMONUMENTATION PROGRAM  
**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**COPY**

For corners in Arbela Township

<u>Tuscola</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>10N</u> R <u>7E</u>	<u>M-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

RECEIVED FOR RECORD  
LIBER NO. \_\_\_\_\_ PAGE NO. \_\_\_\_\_  
FILING NO. #93  
ARBELA TWP  
94 DEC -1 PM 4:26  
VIRGINIA M. McLAUREN  
TUSCOLA COUNTY  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Kenneth D. Dunton, in a field survey on August 27, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2			
3												
4	7		8		9		10		11			
5												
6	18		17		16		15		14			
7												
8	19		20		21		22		23			
9												
10	30		29		28		27		26			
11												
12	31		32		33		34		35			
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

1821 G.L.O. Notes  
Joseph Wampler, D.S.  
Set 1/2 mile post  
Sugar 14 S 78 E 11  
Ironwood 9 N 64 W 24

Note: Found no records of subsequent restoration of corner M-2, T10N-R7E.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found 3/4" pipe in mon. box at extension of old fence line from west. Per note on re-survey of Section 6, T10N-R8E, by G. B. Felton in 1895 an error had been made in the total distance given along the East line of Sec. 1, T10N-R7E (no re-measured distance given) in the U. S. Field Notes. Line trees and runs were found in proper places per original notes, so no chaining errors had taken place along line to run at 68.70 chains. Felton came to this conclusion in 1879 & 1895 as did Mills and Pettibone in 1857 & 1849. Due to 1821 error and no subsequent re-measure to proportion to, I accepted the 3/4" pipe found as the best evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Placed 5/8" iron rod and standard brass cap stamped corner M-2, T10N-R7E in 3/4" pipe found in mon. box. Encased 5/8" rod and brass cap in concrete in mon. box.  
S81°16'W 33.05' set T. C. Remon. tag & spike in SE face t. pole stub.  
N28°31'W 27.35' set 1/2" iron rod & cap #23503 in road shoulder.  
N34°54'E 28.34' set 1/2" iron rod & cap #23503 in road shoulder.  
S36°53'E 27.98' set 1/2" iron rod & cap #23503 in road shoulder.  
N00°20'40"W 196.27' fnd. "T" iron in mon. box apparent Cor. A-2, T10N-R8E.

Signed by [Signature] Date November 21, 1994

Surveyor's Michigan License No. 23503

**APPROVED**  
11-21-94 [Signature]



