

SURVEY & REMONUMENTATION

APR 25 1995

1994 REMONUMENTATION PROGRAM LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

COP

COMMISSION

For corners in Arbela Township

RECEIVED FOR RECORD
 LIBER NO. _____ PAGE NO. _____
 FILING NO. #99
 94 DEC -1 PM 4:26
 VIRGINIA M. McCLAREN
 TUSCOLA COUNTY
 REGISTER OF DEEDS

<u>Tuscola</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>10N</u> R <u>7E</u>	<u>M-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kenneth D. Dunton, in a field survey on August 6, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1821 G.L.O. Notes
Joseph Wampler, D.S.
Set 1/2 mi. post
Beech 11 S70E 16
Sugar 14 North 7

October 28, 1886
John A. Teskey, Surveyor
Proportional Distances
W. Oak 4 N 22 W 94 1/2
Sugar 2 S 44 E ?

May 12, 1978 Witness card by Robt. Woloshen with Rowe Eng., Inc.
Found 1" pipe 3' deep-raised with 1/2" pipe & 1/2" re-rods.
N30°E 6.00' fnd. "T" iron.
N80°W 31.44' fnd. "T" iron.
N80°W 32.24' nail in face post.
N85°W 75.54' #11192 tag 9" elm.
North 113.52' fnd. 1/2" re-rod.
West 33.00' set 1/2" rod & cap #11

Section A continued on back of this form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" rod in 1/2" pipe in mon. box and accepted as the proper position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed standard brass cap over 1/2" iron rod found in monument box. Encased rod & brass cap in concrete in mon. box. Stamped standard brass cap, corner M-8, T10N-R7E.
S78°08'W 11.98' set 1/2" x 18" re-rod in road shoulder.
N89°10'W 33.10' found 1/2" rod & cap #11192.
N86°19'W 75.57' set T. C. Remon. tag & spike in S. face 20" elm.
N79°01'W 31.53' found "T" iron.
N56°15'E 60.00' found spike in W. face 14" elm.
N79°30'W 32.3' top center 8" corner post.
N01°25'E 113.26' found 3/8" iron rod at apparent cor. A-8, T10N-R8E.

Signed by [Signature]
Surveyor's Michigan License No. 23503

Date November 7, 1994

APPROVED
11-7-94



