

SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

1994 REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COPY

For corners in Arbela Township

Tuscola (County)	Located In:	Corner Code ##
1. Public Land Survey	T <u>10N</u> R <u>7E</u>	<u>M-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD
 LIBER NO. _____ PAGE NO. _____
 FILING NO. #101
ARBELA TWP
 94 DEC -1 PM 4:25
 VIRGINIA M. McLAREN
 TUSCOLA COUNTY
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kenneth D. Dunton in a field survey on August 6, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1821 G.L.O. Notes Joseph Wampler, D.S. Set 1/2 mi. post Elm 6 N 64 1/2 W 6 ? 7 S 89 E 7	1959 Witness card from road survey by R. J. Black, #3384. Found 3/4" pipe. S15°E 84.56' spike in root of 14" hickory N85°W 55.27' face of tele. pole N83°W 34.62' spike in root of 8" oak North 80.71' W 1/4 cor. Sec. 30, Millington Township	April 11, 1973 L.C.R.C. form, filed on Page 28, D. T. Rowe, L.S. #11192 Found 3/4" pipe N85°W 55.01' nail & cap t. N83°W 34.72' nail & cap 12" oak N45°W 42.70' nail & cap 10" oak
-----------------------------------------------------------------------------------------------------	------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

Section A continued on back of this form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" pipe in center of rock pile below road surface. Also, found 1/2" pipe 1.75' southwest. Found no evidence below 1/2" pipe. Accepted 3/4" pipe as the proper position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Removed 3/4" pipe & placed 36" concrete monument with standard brass cap stamped corner M-10, T10N-R7E.
 S89°43'50"W 32.54' found "T" iron at base of steel fence post.
 N89°28'W 61.19' set T. C. Remon. tag & spike in S. face 13" hickory.
 N81°55'W 34.63' set T. C. Remon. tag & spike in S. face 16" oak.
 N31°34'W 42.66' set T. C. Remon. tag & spike in E. face 24" oak.
 S79°43'E 17.32' W. leg of steel post (road side reflector).

Signed by [Signature] Date November 7, 1994
 Surveyor's Michigan License No. 23503
APPROVED
11-7-94

 FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1993, REVISED MAY 14, 1993

Section A continued:

April 11, 1972 Survey by D. T. Rowe, L. S. #11192, recorded in Liber 1 of Surveys on Pages 552 & 553, Tuscola County records. Same object and accessories as shown on L. C. R. C., Page 28, Arbela Township.

May 13, 1976 Survey by D. T. Rowe, L. S. #11192, recorded in Liber 461 on Page 179, Tuscola County records. Same object and accessories as shown on L. C. R. C., Page 28, Arbela Township.

June 1, 1994 Survey by Barbara N. Snyder, P. S. #36001, recorded in Liber 660 on Page 202, Tuscola County records. Found 3/4" pipe.

N83°W 34.00' face 16" tree

N45°W 42.50' face 20" oak

West 33' "T" iron

S87°E 17.63' sign post

