

1993

1993 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
TUSCOLA  
(County)

MILLINGTON TOWNSHIP

Located In: Corner Code #

1. Public Land Survey	T 10 N R 8 E	E-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

RECEIVED FOR RECORD  
LIBER NO. \_\_\_\_\_ PAGE NO. 4  
FILING NO. Millington  
03 NOV 19 PM 1:25  
VIRGINIA M. HALL  
TUSCOLA COUNTY  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JONATHAN M. FIELD, in a field survey on OCTOBER 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1821 GLO - WAMPLER, D.S.; SET POST; SUGAR 16" S34W 3LKS., SUGAR 10" N67E 22LKS.
- 1984 EMERY LAND SURVEYING - EMERY, P.S.#24593; SURVEY L.540, PG.562 - SET 1/2" ROD; N15E 40.38' RD SIGN POST, S35E 35.5' TELE PEDESTAL, S15W 21.9' E. LEG OF SIGN, N40W 45.5' STOP SIGN
- 1991 KAY ENG. - BROWN, P.S.#24588; UNRECORDED SURVEY PROJ. NO. 91-69 - FND 1/2" ROD; SAME WITS AS 1984 EMERY SURVEY

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 ROWE ENG. - FIELD, P.S. #37276; FND 1/2" ROD, 3'N & 14'W TO INTERSECTION OF GRAV. RD N. & ASPH. RD E-W  
ACCEPTED 1/2" ROD AS BEST EVIDENCE OF ORIGINAL CORNER LOCATION

COPY

SEE ALSO BACK OF THIS FORM

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-13 REMOVED ROD, SET STANDARD MONUMENT (5/8" ROD W/ BRASS CAP IN CONG, IN MON. BOX)
- N17°E, 40.39' ROAD SIGN POST
- S34°E, 35.79' TOP CENTER OF PHONE RISER
- S20°W, 22.04' E. EDGE OF E. POST OF DIRECTIONAL SIGN
- N35°W, 45.52' STOP SIGN POST
- N38°E, 48.71' SET NAIL W/REMON TAG IN SE FACE FENCE POST
- S29°W, 24.79' SET NAIL W/REMON TAG IN NE FACE 12" POPLAR WEST, 292.50' FND. 1/2" ROD




Signed by Jonathan M. Field  
Surveyor's Michigan License No. 37276

Date 11-8-93

APPROVED  
11-8-93  
J.M.F.

COPY



SECTION 33  
T10N-R8E

SECTION 32  
T10N-R8E

SECTION 4  
T9N-R8E

SECTION 5  
T9N-R8E

