

SURVEY & REMONUMENTATION

FEB 08 2001

SECTION

2000 REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. _____
FILE NO. #102 Millington
00 DEC 20 PM 2:42

Jonathan M. Field
TUSCOLA COUNTY
REGISTER OF DEEDS

For corners in: MILLINGTON TWP.

TUSCOLA (County)	Located In:	Corner Code #
1. Public Land Survey	T 10N R 08E	K-2
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, JONATHAN M. FIELD, in a field survey on AUGUST 17 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
1822 GLO; FLETCHER, D.S.; SET POST; BEECH 20 S72°W 8 LKS., PINE 10 NORTH 22 LKS.
1896 TESKEY, C.S.; PG.282-3; STAKE; PINE 60 NORTH 22 LKS.
1975 LEACH ENG.; LEACH, P.S. #7236; LCRC, PG.37; 3/4" ROD IN MON BOX; N30°E 76.73' W FACE OF TELEPHONE POLE, S20°E 133.30' W FACE OF TELEPHONE POLE, S40°W 51.20' NAIL AND TAG IN NW FACE OF TELEPHONE POLE.
1975 LEACH ENG.; LEACH, P.S. #7236; SURVEY, L.447 PG. 902; MON BOX; WITS REFERENCED TO LCRC PG. 37.
1976 ROWE ENG.; ROWE, P.S. #11192; LCRC, PG.46; 3/4" RE-ROD IN MON BOX; SAME WITS AS 1975 LCRC
1990 SPICER ENG.; PREVOST, P.S. #24612; SURVEY; L.606 PGS.1420, 1424; SAME OBJECT AND WITS AS 1975 LCRC
1990 SPICER ENG.; PREVOST, P.S. #24612; SURVEY; L.607 PG.944; SAME OBJECT AND WITS AS 1975 LCRC
1998 GRAVLIN, P.S.#23510; UNRECORDED SURVEY JOB NO.980157 DATED 9-14-98; SAME AS 1975 LCRC

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
2000 ROWE; FIELD, P.S.#37276 FND. BOAT SPIKE IN MON BOX; 0.3' W. OF C/L SHERIDAN RD. NO DEFINITE OCCUPATION TO E. OR W.; RECOVERED 1 REMAINING WIT WHICH INDICATES THAT FND. ROD IS IN SAME POSITION AS 1975 LCRC CITED IN SECTION A ABOVE.

ACCEPTED FND. ROD IN MON. BOX AS BEST AVAILABLE EVIDENCE OF ORIGINAL CORNER POSITION.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
K-2 SET 5/8" ROD W/ REMON CAP STAMPED K-2 T10N R8E OVER FND. BOAT SPIKE, ENCASED ROD & CAP IN CONC. IN MON BOX
EAST 33.01' FND. PIPE W/CAP #24612
N75°E, 69.01' SET P-K NAIL W/ REMON TAG IN S. FACE P.POLE
S35°W, 51.62' SET P-K NAIL W/REMON TAG IN W. FACE P.POLE
N75°W, 22.89' SET 1/2" ROD W/CAP #37276



Signed by Jonathan M. Field Date 11-10-2000
Surveyor's Michigan License No. 37276

APPROVED 11/8/2000
KUL
RLB

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993

COPY

FEB 08 2001

SECTION

COPY

