

SURVEY & REMONUMENTATION

FEB 08 2001

**2000 REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. _____
FILE NO. #111 Millington
00 DEC 20 PM 2:42

SECTION

For corners in: **MILLINGTON TWP.**

<u>TUSCOLA</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>10N</u> R <u>08E</u>	<u>K-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Jonathan M. Field
TUSCOLA COUNTY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JONATHAN M. FIELD, in a field survey on AUGUST 17 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1822 GLO; FLETCHER D.S.; SET POST; BEECH 16 N1/4E 17 LKS, BEECH 10 S89W 16 LKS.
1882 TESKEY, C.S.; PG.14-5; STAKE AT CORNER; NO WITS GIVEN
1973 ROWE ENG.; ROWE, P.S. #11192; SURVEY, L.2 PG.415; 1/2" ROD; S75°W 30.30' TAG IN APPLE, S40°W 66.30' TAG IN 10" MAPLE, EAST 33.00' "T" IRON
1982 DUNTON LAND SURVEYING; DUNTON, P.S. # 23503; SURVEY, L.527 PG.1441; FND. 5/8" ROD IN MON BOX; EAST 11.5' EDGE OF PAVEMENT, WEST 11.0' EDGE OF PAVEMENT, S25°W 147.15 TAG IN P.POLE
1982 DUNTON LAND SURVEYING; DUNTON, P.S. # 23503; SURVEY, L.529 PG.1416; SAME AS 1982 SURVEY
1987 KAY ENG.; BROWN, P.S. #24588; SURVEY, L.578 PG.721; SAME AS 1982 SURVEY
1992 ROWE ENG.; FIELD, P.S. #37276; SURVEY, L.632 PG.1335; FND. 5/8" ROD IN MON BOX; S25°W 147.15' NAIL W/TAG IN P.POLE, N80°E 63.62' NAIL IN 8" ELM, WEST 59.20' NAIL IN 8" ELM, S80°E 98.68 NAIL IN TWIN 8" ELM
1993 ROWE ENG.; FIELD, P.S. #37276; SURVEY, L.645 PG.950; SAME AS 1992 SURVEY
1994 ROWE ENG.; FIELD, P.S. #37276; SURVEY, L.667 PG.987; SAME AS 1992 SURVEY

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
2000 ROWE, FIELD, P.S.#37276; FND. 3/4" PIPE IN MON BOX; 0.5' W. OF C/L SHERIDAN RD., FENCE & TREE LINE TO E. & W.; RECOVERED 3 PREVIOUS WITS WHICH INDICATE THAT FND.PIPE IS IN SAME POSITION AS 1982 SURVEY CITED ABOVE.

ACCEPTED FND.PIPE IN MON. BOX AS BEST AVAILABLE EVIDENCE OF ORIGINAL CORNER POSITION.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
K-8 SET 5/8" ROD W/ REMON CAP STAMPED K-8 T10N R8E INSIDE FND. PIPE, ENCASED ROD, CAP & PIPE IN CONC. IN MON BOX
S25°W 147.15' NAIL W/TAG #11192 IN E. FACE P.POLE
N80°E 63.62' NAIL IN S. FACE 8" ELM
WEST 59' CENTER OF 10" ELM STUMP
S80°E 98.68' NAIL IN S. FACE TWIN 10" ELM
N70°E 54.94' NAIL W/TAG IN S. FACE 8" ELM



Signed by Jonathan M. Field Date 11-10-2000
Surveyor's Michigan License No. 37276

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 18, 1971
REVISED MAY 14, 1978
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993

APPROVED
11/8/2000
[Handwritten initials]

COPY

