

SURVEY & REMONUMENTATION

FEB 08 2001

SECTION

2000 REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. _____
FILE NO. #114 Millington

00 DEC 20 PM 2:45

Gregory McQueen
TUSCOLA COUNTY
REGISTER OF DEEDS

For corners in: MILLINGTON TWP.

TUSCOLA (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>10N</u> R <u>08E</u>	<u>K-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____	Recorded Plat _____	
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Mark W. Powell, P.S., in a field survey on AUGUST 17 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1822 GLO; FLETCHER, D.S.; SET POST; SUGAR 10 S27E 17 LKS., BEECH 12 S46W 23 LKS.
1972 H.B.E.; HENDERSON, P.S. #16043; SURVEY, L2 PG.232; SET 1/2" IRON; N80°W 62.85' CLUMP POPLAR, S85°W 33.05' P.POLE
1972 HENDERSON, P.S. #16043; LCRC, PG.15; SAME AS 1972 ABOVE (SET ON LINE 1/2 WAY BETWEEN NE & SE COR)
1979 DUNTON, P.S. #23503; SURVEY L.498 PG.754; FND. 5/8" ROD IN MON BOX; S25W 130.70 PK IN P.POLE, S80E 45.5' S END 12" CMP, N80E 54.2' N END 12" CMP
1982 DUNTON, P.S. #23503; LCRC, PG.57; SAME AS 1979 SURVEY
1983 EMERY, P.S. #24593; SURVEY L.536 PG. 662; FND. IRON ROD IN MON BOX; SAME AS 1979 SURVEY
1996 H.B.E.; ELRICH, P.S. #18986; SURVEY, L.694 PG. 1380; FND. 3/4" IRON IN MON BOX; S80E 119.39' PK NAIL IN 14" WALNUT, N65E 49.47' PK NAIL IN COR. POST, S30W 130.66' PK NAIL IN P.POLE, N15°W 237.66' PK NAIL IN P.POLE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
2000 ROWE; Powell, P.S. ; FND. 5/8" ROD IN MON BOX; 2.5' W. OF C/L SHERIDAN RD., TREE LINE TO W., C/L OLD PEDLOW RD. TO E.; RECOVERED 3 PREVIOUS WITS WHICH INDICATE THAT FND. ROD IS IN SAME POSITION AS 1979 SURVEY CITED IN SECTION A. ABOVE.

ACCEPTED FND. ROD IN MON. BOX AS BEST AVAILABLE EVIDENCE OF ORIGINAL CORNER POSITION.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
K-10 SET 5/8" ROD W/ REMON CAP STAMPED K-10 T10N R8E FND. ROD, ENCASED ROD & CAP IN CONC. IN MON BOX OVER (CAP STAMPED P.S. #37276)
S25°W 130.70' P-K NAIL IN SE FACE P.POLE
S80°E 45.48' S. END 12" CMP
N80°E 54.16' N. END 12" CMP
S80°E 119.39' P-K NAIL IN N. FACE 24" WALNUT
N65°E 49.99' P-K NAIL IN SW FACE FENCE COR. POST
N15°W 237.29' P-K NAIL IN E. FACE P.POLE



Signed by Mark W Powell Date 12-19-00
Surveyor's Michigan License No. 44298

FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS, JAN. 26, 1971
REVISED MAY 14, 1976
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993

**APPROVED BY TUSCOLA COUNTY
REMONUMENTATION PEER GROUP**
1210412000

*1500
KML
Rott*

COPY

REVISION INFORMATION SHEET
REMOVED BY INZODEN SURVEY

COPY

**SURVEY &
REMONUMENTATION**

FEB 08 2001

SECTION

K-10, T10N-R8E

