

SURVEY & REMONUMENTATION

FEB 08 2001

SECTION

**2000 REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. _____
FILE NO. #100 Millington

00 DEC 20 PM 2:41

James J. Millington
TUSCOLA COUNTY
REGISTER OF DEEDS

For corners in: **MILLINGTON TWP.**

<u>TUSCOLA</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>10N</u> R <u>08E</u>	<u>L-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, MARK W. POWELL, P.S., in a field survey on AUGUST 17 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
GLO; NOT SET

1981 LEACH ENG.; LEACH, P.S. #7236; SURVEY, L.513 PG.1383-4; SET T-IRON; EAST 49.52' S 1/4 COR SEC 36 T11N R8E, S2W 613.48' RAILROAD SPIKE, S88W 31.08' FND T-IRON

1981 LEACH ENG.; LEACH, P.S. #7236; LCRC PG.56; SAME AS 1981 SURVEY (SET AT EXTENSION OF OCC. N-S 1/4 LINE & N. SECTION LINE)

1994 HURON SURVEYING; BROWN, P.S. # 24588; SURVEY, L.665 PG. 693-4; FND. 1/2" ROD; S10E 25.59' SPIKE W SIDE 7" OAK, EAST 10.80' SPIKE NORTH SIDE 12" BIRCH, N15E 13.55' SPIKE W SIDE 6" BIRCH

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

2000 ROWE; POWELL, P.S. ; FND. 1/2" ROD W/ CAP #24588 1.12' N. OF S. LINE OF T11N-R8E; RECOVERED 1 PREVIOUS WIT WHICH INDICATES THAT FND. ROD IS IN SAME POSITION AS 1981 SURVEY CITED ABOVE.

PREVIOUSLY ESTABLISHED

ACCEPTED FND. ROD AS BEST AVAILABLE EVIDENCE OF CORNER POSITION (NOW HOLDING AS AMENDED MONUMENT).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-1 SET STD. REMON MONUMENT STAMPED L 1 T10N R8E ON S. LINE OF T11N-R8E (CAP STAMPED P.S. 37276)
S85°W, 29.74' FND. T-IRON
N86°E, 50.89' FND. TUSCOLA CO. MONUMENT AT L-13 T11N-R8E
SOUTH, 1.12' FND. 1/2" ROD W/CAP #24588

Signed by Mark W Powell Date 12-19-00

Surveyor's Michigan License No. 44298



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 24, 1971
REVISED MAY 14, 1976
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993

APPROVED
11/8/2000
EMC
RCB

COPY

SURVEY &
REMONUMENTATION

FEB 08 2001

SECTION

COPY

L-1 TION-R8E

