

SURVEY & REMONUMENTATION

FEB 08 2001

**2000 REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. _____
FILE NO. # 116 Millington
00 DEC 20 PM 2:45

SECTION

For corners in: **MILLINGTON TWP.**

<u>TUSCOLA</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>10N</u> R <u>08E</u>	<u>L-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Ann M. Schen
TUSCOLA COUNTY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, MARK W. POWELL, P.S., in a field survey on DECEMBER 5 2000 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1822 GLO; FLETCHER D.S.; SET POST; BEECH 9 N10E 30 LKS., B. OAK 9 N7W 19 LKS.
1900 FELTON, C.S.; PG. 10-13; "SET BY ME FROM BT's IN 1879 & NOW IDENTIFIED". CEDAR POST, IRON KETTLE & TILE AT CORNER; B. CHERRY 10 S28E 64FT., B. ASH 12 S471/2W 17.2FT.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
2000 ROWE; POWELL, P.S.#44298; POSITION FALLS IN SWAMP, FOUND NOTHING. REESTABLISHED CORNER POSITION BY PROPORTIONATE MEASUREMENT BETWEEN K-11 AND M-11 AND INTERSECTING WITH A PROPORTIONATE MEASUREMENT NORTH FROM RECOVERED BUGGY AXLE CORNER (1900 C.S. MONUMENT) AT INTERIOR 1/4 CORNER OF SECTION 36 (L-12).

ACCEPTED POSITION THUS REESTABLISHED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE ORIGINAL CORNER POSITION.

SET WITNESS MONUMENT AND CARSONITE POST ALONGSIDE 150.00' W ESTERLY OF CORNER POSITION L-11 AND ON LINE BETWEEN CORNER K-11 AND L-11

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
L-11 WC (150.00' W.) SET STD. REMON MONUMENT WCAP STAMPED L-11 W.C. T10N R8E, AND CARSONITE POST ALONGSIDE.

WITNESSES TO WITNESS MONUMENT

- S85E 20.29' SET NAIL AND REMON TAG N. FACE 10" BIRCH
- S85W 18.75' SET NAIL AND REMON TAG NW. FACE 10" OAK
- N85W 7.75' SET NAIL AND REMON TAG N. FACE 6" OAK
- N45E 9.79' SET NAIL AND REMON TAG NW FACE 12" POPLAR



Signed by Mark W Powell Date 12-14-00
Surveyor's Michigan License No. 44298

FORM APPROVED BY MICHIGAN STATE BOARD OF SURVEYORS, JAN. 22, 1971
REVISED MAY 14, 1976
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993

**APPROVED BY TUSCOLA COUNTY
REMONUMENTATION PEER GROUP**

12/13/2000

*ADD
RLB
KML*

COPY

SURVEY &
REMONUMENTATION

FEB 08 2001

COPY

SECTION 36

L-11, T10N-R8E
SECTION 36
T10N-R8E

RAW CLOSURE = 1:22,496

2000 ROWE INFORMATION AS SHOWN
IS COMPASS RULE ADJUSTED DATA
FOR THIS SECTION

