

FEB 08 2001

2000 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. _____
FILE NO. #101 Millington
00 DEC 20 PM 2:11

SECTION

For corners in: MILLINGTON TOWNSHIP

<u>TUSCOLA</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>10N</u> R <u>08E</u>	<u>M-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Seg. 2

Gregory M. ...
TUSCOLA COUNTY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

I, MARK W. POWELL, P.S., in a field survey on AUGUST 17, 2000 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1821 GLO; WAMPLER D.S.; SET POST; SPRUCE 8 N03E 2 LKS., SPRUCE 6 N78E 6 LKS.
1996 DUNTON, P.S.#23503; 1996 REMONUMENTATION LCRC PG 97; SET MONUMENT

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
2000 ROWE; POWELL, PS #44298; FOUND TUSCOLA COUNTY MONUMENT 3' BELOW ASPHALT ROAD SURFACE.; RECOVERED 1 PREVIOUS WITNESS WHICH INDICATES THAT THE FOUND MONUMENT IS IN THE SAME POSITION AS IN THE 1996 LCRC CITED IN SECTION A. ABOVE.

ACCEPT FOUND TUSCOLA COUNTY MONUMENT AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

COPY

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-1 RAISED POSITION OF FOUND MONUMENT WITH 4" CONCRETE MONUMENT WITH REMON CAP STAMPED M-1 T10N-R8E AND INSTALLED MONUMENT BOX (CAP STAMPED P.S. #37276)
S85E 63.27' SET T.C. REMON TAG N. FACE 4" OAK
S40E 79.40' SET T.C. REMON TAG SW. FACE 6" ASH
S70W 42.16' SET T.C. REMON TAG S. FACE 8" ASH
N85W 59.14' FOUND T.C. REMON TAG NE. FACE 8" OAK



Signed by Mark W Powell
Surveyor's Michigan License No. 44298

Date 12-19-00

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISIONS: REVISED MAY 14, 1975
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993

APPROVED BY TUSCOLA COUNTY
REMONUMENTATION PEER GROUP
12/13/2000
KML

SURVEY &
REMONUMENTATION

FEB 08 2004

COPY

SECTION

M-1 TION-R8E

