

OCT 20 1994

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970
1994 REMONUMENTATION PROGRAM

COMMISSION

For corners in Watertown Twp.
TUSCOLA
(County)

Located In:

Corner Code #

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. _____
FILING NO. #60
WATERTOWN TWP.
94 OCT 10 AM 8:47
VIRGINIA H. HOLLAREN
TUSCOLA COUNTY
REGISTER OF DEEDS

COPY

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 10N R 09E M-4
- T _____ R _____
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, JONATHAN M. FIELD, in a field survey on JULY 17 19 94
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	I
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
1834 GLO; PARKE, D.S.; SET POST; BEECH 7 S26W 6 1/2LKS., BEECH 8 N29 1/2W 29LKS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1994 ROWE ENG. - FIELD, P.S.#37276; FND 1/2" ROD ON C/L GRAVEL ROAD N-S, FIELD LINE TO E. & FENCE/BRUSH ROW TO W.

ACCEPTED 1/2" ROD AS BEST EVIDENCE OF ORIGINAL CORNER POSITION

SEE ALSO BACK OF THIS FORM

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-4 REMOVED ROD, SET STANDARD MONUMENT (5/8"X36" ROD W/ BRASS CAP IN CONC.)

- S81°E, 28.88' TOP CENTER OF PHONE RISER
- S84°E, 50.90' SET NAIL W/REMON TAG ABOVE FND NAIL W/FLAG IN N. FACE 8" DOGWOOD
- S53°E, 34.19' SET NAIL W/REMON TAG IN SE FACE 8" ASH
- S16°W, 120.05' SET NAIL W/REMON TAG IN SE FACE 28" MAPLE
- S86°W, 28.60' TOP CENTER OF PHONE RISER
- S72°W, 110.08' NE CORNER OF HOUSE #9245



Signed by Jonathan M. Field Date 9-2-94
Surveyor's Michigan License No. 37276

APPROVED
S-31-94
[Signature]

SWAFFER ROAD

M-3

NE 1/4
SEC. 12
T10N-R9E

1834 GLO 2640'
1994 REI 2641.82'

180°08'45"

M-4

WILLITS ROAD

SE 1/4
SEC. 12
T10N-R9E

1834 GLO 2640'
1994 REI 2648.51'

180°01'07"

M-5

MURPHY LAKE ROAD

