

OCT 26 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

1994 REMONUMENTATION PROGRAM

For corners in Watertown Twp.

TUSCOLA

(County)

Located In:

Corner Code #

COPY

VIRGINIA H. McLAUREN
TUSCOLA COUNTY
REGISTER OF DEEDS

WATERTOWN TWP
94 OCT 10 AM 8:47

RECEIVED FOR RECORD
LIBER NO. PAGE NO.
FILING NO. #61

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 10N R 09E
- 2. Property Controlling in Section S T R
- 3. Miscellaneous Property in Sec. S T R

M-5

- 4. Lot No. Recorded Plat
- 5. Private Claims

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JONATHAN M. FIELD, in a field survey on JULY 17 19 94 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 - 1834 GLO; PARKE, D.S.; SET POST; BEECH 8 S65W 22LKS., BEECH 12 N44W 21 1/2LKS. GLO NOTES OF T10N-R10E INDICATE THAT CORNER IS COMMON TO BOTH TOWNSHIPS
 - 1972 HENDERSON, P.S.#16043; LCRC 7; SET 1/2" IRON @ C/L ROADS; N45°E 59.82' P.POLE, S45°W 39.96' RD SIGN, N30°W 140.60' P.POLE
 - 1987 GRAVLIN, P.S.#23510; SURVEY L.7, PG.739; FND 1/2" IRON; N45°E 59.79' SPIKE IN T.POLE, S50°W 41.95' RD SIGN POST, S25°E 157.77 P-K IN T.POLE
 - 1989 GRAVLIN, P.S.#23510; LCRC L.004, PG.261; FND 1/2" IRON; WITS SAME AS 1987 SURVEY

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 - 1994 ROWE ENG. - FIELD, P.S.#37276; FND 1/2" ROD
 - 2 PREVIOUS WITNESSES INDICATE THAT 1/2" ROD IS IN SAME POSITION AS 1972 HENDERSON IRON
 - ACCEPTED 1/2" ROD AS BEST EVIDENCE OF ORIGINAL CORNER POSITION

SEE ALSO BACK OF THIS FORM

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 - M-5 REMOVED 1/2" ROD, SET STANDARD MONUMENT (5/8"X36" ROD W/ BRASS CAP IN CONC.)
 - N55°E, 59.57' FND NAIL W/DISK IN NW FACE T.POLE
 - N33°W, 138.42' SET NAIL W/REMON TAG ABOVE FND NAIL W/FLAG IN E. FACE P.POLE
 - S59°W, 42.08' CENTER OF ROAD SIGN POST
 - S28°W, 157.38' SET NAIL W/REMON TAG IN NW FACE P.POLE
 - S18°E, 157.94' FND P-K NAIL IN W. FACE T.POLE



Signed by Jonathan M. Field Date 9-2-94

Surveyors Michigan License No. 37276

APPROVED 8-31-94 [Signature]

