

OCT 20 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970
1994 REMONUMENTATION PROGRAM

For corners in Watertown Twp.

TUSCOLA
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 10N R 09E
- 2. Property Controlling in Section S T R
- 3. Miscellaneous Property in Sec. S T R

M-7

COPY

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. _____
FILING NO. # 63
WATERTOWN TWP
94 OCT 10 AM 8:48
VIRGINIA H. HOLLAREN
TUSCOLA COUNTY
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JONATHAN M. FIELD, in a field survey on JULY 17 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 1834 GLO; PARKE, D.S.; SET POST; BEECH 9 N22E 62LKS., HEMLOCK 24 S70W 30LKS.
 GLO NOTES OF T10N-R10E INDICATE THAT CORNER IS COMMON TO BOTH TOWNSHIPS
 1972 HENDERSON; P.S.#16043; LCRC 8; FND PIPE; NE 59.13' P.POLE, S45°E 51.37' P.POLE, S50°W 61.33' PROJECT MARKER, NW 44.9' ROAD SIGN
 1974 SWARTS, P.S.#16945; LCRC L.002, PG.761; FND 1/2" REBAR; WITS SAME AS 1972 LCRC ABOVE
 1989 GRAVLIN SURVEYING; GRAVLIN, P.S.#23510; SURVEY L.598, PG.572; FND PIPE; WITS SAME AS 1972 LCRC ABOVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1994 ROWE ENG. - FIELD, P.S.#37276; FND 1/2" ROD (BENT) DRIVEN INSIDE 3/4" PIPE
 3 PREVIOUS WITNESSES INDICATE THAT 1/2" ROD IS IN SAME POSITION AS 1972 HENDERSON IRON
 ACCEPTED 1/2" ROD AS BEST EVIDENCE OF ORIGINAL CORNER POSITION

SEE ALSO BACK OF THIS FORM

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 M-7 REMOVED ROD, SET STANDARD MONUMENT (5/8"X36" ROD W/BRASS CAP IN CONC.)
 N60°E, 59.01' FND P-K NAIL W/DISK IN S. FACE T.POLE
 N60°E, 59.23' FND NAIL W/DISK IN SE FACE T.POLE
 S55°W, 61.04' TOP CENTER OF CONC. PROJECT MARKER POST
 N50°W, 47.77' CENTER OF ROAD SIGN POST
 S28°E, 41.42' W. EDGE OF STOP SIGN POST
 S36°E, 51.35' FND. NAIL W/TAG IN NE FACE T.POLE
 S35°E, 51.07' FND D.H. NAIL IN NW FACE T.POLE



Signed by Jonathan M. Field Date 9-2-94

Surveyor's Michigan License No. 37276

APPROVED
2-31-94
J.M.F.

