

OCT 20 1994

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970
1994 REMONUMENTATION PROGRAM

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. _____
FILING NO. #65
WATERTOWN TWP
94 OCT 10 AM 8:48
VIRGINIA H. McLAUGHLIN
TUSCOLA COUNTY
REGISTER OF DEEDS

COMMISSION
For corners in Watertown Twp.
TUSCOLA
(County)

Located In:

Corner Code #

1. Public Land Survey	T	10N	R	09E	M-9
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S	T	R		
	S	T	R		
3. Miscellaneous Property in Sec.	S	T	R		
	S	T	R		

COPY

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, JONATHAN M. FIELD, in a field survey on JULY 17 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1834 GLO; PARKE, D.S.; SET POST; LYNN 28 S41W 26LKS., HEMLOCK 7 N31W 26LKS., HEMLOCK 16 N88W 15LKS. GLO NOTES OF T10N-R10E INDICATE CORNER IS COMMON TO BOTH TOWNSHIPS
- 1906 BRUMLEY, C.S.; STONE AT COR.; SUGAR 8 S22E 125LKS., ELM 12 S10W 206LKS.
- 1974 SWARTS, P.S.#16945; LCRC 23; SET 1/2" IRON BY DBL PROPORTION; N40°E 77.15' NAIL IN P.POLE S60°E 47.64' NAIL IN P.POLE, S45°W 41.34' NAIL IN P.POLE
- 1988 DAVIS, P.S.#22430; LCRC L.004, PG.189; FND 1/2" IRON; N45°W 66.37' P-K NAIL TWIN 6" TREE, N30°E 47.41' P-K NAIL 8" TREE, N45°E 78.35' P-K NAIL P.POLE
- 1990 ROWE ENG.; OWENS, P.S.#20709; SURVEY L.609, PG.420; FND ROD LYING FLAT - SET ROD W/CAP #33134; N40°E 76.39' NAIL P.POLE, N40°W 42.04' NAIL CUT-OFF T.POLE, S60°E 47.64' NAIL CUT-OFF T.POLE, S45°W 41.34' NAIL IN CUT-OFF T.POLE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 ROWE ENG. - FIELD, P.S.#37276; FND 1/2" ROD W/CAP #33134 3.5' S. OF C/L ASPH. ROAD W. GRAVEL ROAD E. & 3' W. OF C/L GRAVEL ROAD N-S 2 PREVIOUS WITNESSES INDICATE THAT 1/2" ROD IS IN SAME POSITION AS 1974 SWARTS IRON

ACCEPTED 1/2" ROD AS BEST EVIDENCE OF ORIGINAL CORNER POSITION

SEE ALSO BACK OF THIS FORM

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-9 REMOVED ROD, SET STANDARD MONUMENT (5/8"X36" ROD W/ BRASS CAP IN CONC., IN MON. BOX)
- N45°E, 76.37' SET NAIL W/REMON TAG ABOVE FND NAIL W/FLAG IN SE FACE P.POLE
- S54°E, 47.66' SET NAIL W/REMON TAG ABOVE FND P-K NAIL W/FLAG IN NE FACE CUT-OFF T.POLE.
- S33°E, 53.26' SET NAIL W/REMON TAG IN W. FACE 10" ELM
- S08°W, 132.4' CENTER OF 30" STUMP
- S45°W, 41.34' SET NAIL W/REMON TAG ABOVE FND P-K NAIL W/FLAG IN E FACE CUT-OFF T.POLE
- N42°W, 78.02' SET NAIL W/REMON TAG ABOVE FND NAIL W/FLAG IN NE FACE 28" ELM
- N32°W, 41.97' SET NAIL W/REMON TAG ABOVE FND P-K NAIL W/FLAG IN SE FACE CUT-OFF T.POLE

Signed by Jonathan M. Field Date 9-2-94
Surveyor's Michigan License No. 37276

APPROVED
8-31-94
[Handwritten signatures]

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JULY 28, 1971
REVISOR J.N. 1983
NO PROCESSING FEE
37276



