

SURVEY &  
REMONUMENTATION

COPY

OCT 20 1994

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

1994 REMONUMENTATION PROGRAM

For corners in Watertown Twp.  
TUSCOLA  
(County)

Located in:

Corner Code #

1. Public Land Survey	T 10N R 09E	M-10
	T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

RECEIVED FOR RECORD  
LIBER NO. \_\_\_\_\_ PAGE NO. \_\_\_\_\_  
FILING NO. # 66  
WATERTOWN TWP  
94 OCT 10 AM 8:48  
VIRGINIA H. HOLLAND  
TUSCOLA COUNTY  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, JONATHAN M. FIELD, in a field survey on JULY 17 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1834 GLO; PARKE, D.S.; SET POST; CEDAR 10 S13W 28LKS., PINE 8 N3W 11LKS.
- 1906 BRUMLEY, C.S.; C.P. & STONES AT COR.; ELM 6 N12E 1.24; C.P. N45W 50LKS.
- 1972 ROWE ENG.; ROWE, P.S.#11192; SURVEY L.2, PG.11-12; FND 4" WOOD POST - SET T-IRON; EAST 25.1' COR. POST, S75°E 55.05' NAIL W/CAP 15" BIRCH, S10°E 86.12' NAIL W/CAP 10" ASH, S25°W 85.18' NAIL W/CAP 10" CEDAR
- 1972 HENDERSON-BATES; ELRICH, P.S.#18986; SURVEY L.1, PG.608; FND T-BAR; EAST 25.52' FE POST, S25°E 57.63' TREE, S60°W 34.05' RD SIGN
- 1972 ELRICH, P.S.#18986; LCRC 9; FND T-BAR; SAME WITS AS 1972 H-B SURVEY ABOVE
- 1972 HENDERSON-BATES; ELRICH, P.S.#18986; SURVEY L.2, PG.230; FND T-IRON; SAME WITS AS 1972
- 1977 BECK-GRAVLIN; GRAVLIN, P.S.#23510; SURVEY L.476, PG.219; FND T-IRON; SAME WITS AS 1972
- 1985 ROWE ENG.; OWENS, P.S.#20709; SURVEY L.552, PG.1011-1014; FND T-IRON; NO WITS GIVEN

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1994 ROWE ENG. - FIELD, P.S.#37276; FND 1/2" ROD ABOVE REMNANTS OF WOOD POST 2'S. OF C/L GRAVEL ROAD W. & ON C/L GRAVEL ROAD N-S

ACCEPTED 1/2" ROD AS BEST EVIDENCE OF ORIGINAL CORNER POSITION

SEE ALSO BACK OF THIS FORM

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-10 REMOVED 1/2" ROD, SET STANDARD MONUMENT (5/8"X36" ROD W/ BRASS CAP IN CONC.)
- S72°W, 35.49' N. EDGE OF STOP SIGN POST
- S75°W, 52.73' SET CHIS. NOTCH IN TOP S. END 15" CSP
- N71°W, 52.45' SET CHIS. NOTCH IN TOP N. END 15" CSP
- S68°E, 19.33' CENTER OF ROAD SIGN POST
- S14°E, 86.49' SET NAIL W/REMON TAG IN W. FACE CLUMP ASH
- N33°E, 26.51' FND CHIS. NOTCH IN TOP E. END 15" CSP



Signed by Jonathan M. Field

Date 9-2-94

Surveyor's Michigan License No. 37276

APPROVED 1500  
8-31-94 J.M.F.

SECTION A.

- 1987 HENDERSON-BATES; ELRICH, P.S.#18986; SURVEY L.575, PG.321; FND T-BAR; N75E 54.08' 13" ELM, N75W 52.48' N. END 15" CMP, S75W 52.62' S. END 15" CMP, N85E 13.92' N. LEG SIGN
- 1988 ROWE ENG; WIT CARD; FND T-IRON; N60E 54.01' NAIL 16" ELM, N25W 56.96' NAIL W/TAG #11192 8" ELM, S60E 58.33' NAIL W/TAG #11192 10" MAPLE
- 1990 ROWE ENG.; OWENS, P.S.#20709; SURVEY L.609, PG.420; FND T-IRON; SAME WITS AS 1988 WIT CARD + N80E 30.59' NAIL 3" ELM
- 1991 HENDERSON-BATES; ELRICH, P.S.#18986; SURVEY L.009, PG.608-610; A-10; SET 1/2" IRON FROM TIES; N75E 54.08' NAIL 14" ELM; N75W 52.48' N END 15" CMP, S75W 52.62' S END 15" CMP, N30W 56.78' NAIL W/TAG 6" WILLOW RE-ROD; SAME WITS AS 1972 REI SURVEY.
- 1991 ELRICH, P.S.#18986; LCRC L.004, PG.392; SET 1/2" IRON FROM TIES; SAME WITS AS 1991 SURVEY ABOVE.
- 1992 ROWE ENG.; WIT CARD; FND 1/2" ROD; N60E 53.97' NAIL 16" ELM, N25W 56.78' NAIL W/TAG #11192 8" ELM, S60E 58.57' NAIL W/TAG #11192 10" MAPLE, N80E 30.54' NAIL 3" ELM.

