

**1995 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in Tuscola Township

<u>Tuscola</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>11N</u> R <u>7E</u>	<u>M-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD  
LIBER NO. \_\_\_\_\_ PAGE NO. \_\_\_\_\_  
FILING NO. # 7:7  
TUSCOLA TWP  
95 OCT -5 PM 2:09  
VIRGINIA H. MCCLAREN  
TUSCOLA COUNTY  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kenneth D. Dunton, in a field survey on June 17, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

1821 G.L.O. Notes  
Joseph Wampler, D.S.  
Set 1/4 Section Post  
Hemlock 12" N49W 3  
Ironwood 7" S86E 15

June 10, 1991 Tuscola County Road Commission field notes. Excavated 4'x5' hole to original grade and found nothing. Set rod & monument box by single proportion and on line between NE & SE corners Section 24. No witnesses. Sept. 18, 1991 Survey by J. Field, L.S. #37276 with Rowe Eng., Inc. recorded in Liber 613 on Pages 1038 through 1044 Tuscola County Records. Fnd. 1/2" rod in mon. box @ E 1/4 corner Sec. 24, T11N-R8E @ 168.89' South of W 1/4 corner Sec. 19, T11N-R8E.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found 1/2" re-rod in monument box and accepted as the proper position of the corner.

SURVEY &  
RECORDATION  
DIVISION  
DEC 4 1995  
COMMISSION

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**


Placed standard brass cap stamped corner M-8, T11N-R7E, over 1/2 rerod found in mon. box. Encased rod and cap in concrete in mon. box.  
S56°37'W 23.37' fnd. 1/2" re-rod & cap #37276 in road shoulder.  
N43°35'W 28.06' fnd. 1/2" re-rod & cap #37276 in road shoulder.  
N39°21'E 27.90' fnd. 1/2" re-rod & cap #37276 in road shoulder.  
S36°48'E 26.89' fnd. 1/2" re-rod & cap #37276 in road shoulder.  
West 1.75' physical centerline N-S pavement.  
N00°25'40"W 168.89' apparent corner A-8, T11N-R8E. Fnd. 1/2 re-rod in mon. box.

COPY

Signed by [Signature] Date 10-2-95  
Surveyor's Michigan License No. 23503

APPROVED  
10-2-95

STATE OF MICHIGAN  
KENNETH D. DUNTON  
LAND SURVEYOR  
No. 23503  
LICENSED PROFESSIONAL  
FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28 1971  
REVISED MAY 1975  
REVISED JAN 1993



T11N-R7E

T11N-R8E

1821 Mampler 2640'  
1991 Tuscola Co. Road 2625.72'  
1995 Dunton 2625.66'

Apparent cor. A-8, T11N-R8E  
Fnd. 1/2" rerod in mon. box.

1991 T.C.R.C. 180°00'00"  
1995 Dunton 180°00'00"

1995 Dunton 168.89'

Section 24

1821 Mampler 2640'  
1991 Tuscola Co. Road 2625.72'  
1995 Dunton 2625.63'

Township Line

Section 19

M-9

M-7

M-8

