

**SURVEY &  
REMONUMENTATION**

APR 25 1995

COMMISSION

**COPY**

1994 REMONUMENTATION PROGRAM  
**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD  
LIBER NO. \_\_\_\_\_ PAGE NO. \_\_\_\_\_  
FILING NO. #67  
TUSCOLA TWP  
94 DEC -7 PM 4: 25  
VIRGINIA M. MELAREN  
TUSCOLA COUNTY  
REGISTER OF DEEDS

For corners in Tuscola Township

| Tuscola<br>(County)                   | Located In:             | Corner Code -# |
|---------------------------------------|-------------------------|----------------|
| 1. Public Land Survey                 | T 11N R 7E              | M-11           |
|                                       | T _____ R _____         | _____          |
|                                       | T _____ R _____         | _____          |
|                                       | T _____ R _____         | _____          |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____ | _____          |
|                                       | S _____ T _____ R _____ | _____          |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____ | _____          |
|                                       | S _____ T _____ R _____ | _____          |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kenneth D. Dunton, in a field survey on Oct. 30, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

|                                  |   |
|----------------------------------|---|
| 1821 G.L.O. Notes                | May 10, 1976 Land Cor. Rec. Cert. filed on Page 24, Tuscola Township by Arthur H. Leach, L.S. #7236. Fnd. p.k. nail, set 3" |
| Joseph Wampler, D.S.             | "T" iron flush with blacktop in centerline road.  |
| Set post corner to Secs. 25 & 36 | North 132.25' to 5/8" pipe = SW cor. Sec. 30, T11N-R8E.   |
| Ash 12 S 71 1/2 E 13             | East 25.55' to sign, N. leg.  |
| Beech - N 72 1/2 W 12            | N40°W 40.00' to sign post.  |

Sec. A continued on back of this form.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" iron rod in mon. box and accepted as the proper position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed standard brass cap stamped corner M-11, T11N-R7E on 5/8" re-rod over 3/4" iron rod found in mon. box. Encased rod & brass cap in concrete in mon. box.  
S50°32'W 32.99' fnd. 1/2" rod & cap #33134 in road shoulder.  
N40°47'W 35.47' fnd. 1/2" rod & cap #20709 in road shoulder.  
N48°01'E 34.55' fnd. 1/2" rod in road shoulder.  
S40°32'E 40.75' set 1/2" x 18" rod & cap #23503 in road shoulder.  
N00°15'00"E 130.99' fnd. 1/2" pipe in mon. box at apparent cor. A-11, T11N-R8E.

Signed by




Date

Surveyor's Michigan License No. 23503

APPROVED  
12-05-94

*L.P.E.*  
*DM*



Section A continued:

May 15, 1976 Survey by Arthur H. Leach, L.S. #7236, recorded in Liber 460 on Page 274, Tuscola County records. Set "T" iron. Accessories same as L.C.R.C. Page 24.

July 26, 1979 Surveys by Arthur H. Leach, L.S. #7236, recorded in Liber 499 on Pages 991 & 992 and Liber 499 on Page 993, Tuscola County records. Fnd. "T" iron. Accessories same as L.C.R.C. Page 24.

Aug. 13, 1987 Survey by Jack N. Owens, L.S. #20709, with Rowe Eng. Inc., recorded in Liber 577 on Page 1489, Tuscola County records. Fnd. "T" iron.  
 N45°E 34.53' set rod & cap #20709 in road shoulder.  
 N45°W 35.35' set rod & cap #20709 in road shoulder.  
 S45°E 47.64' set rod & cap #20709 in road shoulder.  
 S50°W 31.98' set rod & cap #20709 in road shoulder.

Aug. 26, 1987 Survey by Brian D. Ferguson, L.S. #26454, recorded in Liber 575 on Page 1173, Tuscola County records. "T" iron. N - 132.25' - 5/8" pipe (SW cor. Sec. 30, T11N-R8E).  
 E - 25.55' - N. leg of street sign.  
 N40°W - 40.0' street sign post.

Dec. 11, 1987 Survey by Brian D. Ferguson, L.S. #26454, recorded in Liber 578 on Page 729, Tuscola County records. "T" iron. Accessories same as Liber 575, Page 1173.

May 8, 1990 Survey by Paul N. Brown, L.S. #33134 with Rowe Eng. Inc., recorded in Liber 604 on Pages 1378 & 1379, Tuscola County records. Fnd. "T" iron.  
 S65°W 42.33' top center of gas test pipe w/sign.  
 S60°E 44.23' N. edge of N. leg stop sign post.  
 North 130.94' fnd. 1/2" pipe at SW cor. Sec. 30, T11N-R8E.  
 N00°07'56"W 2621.19' E. 1/4 cor. Sec. 25.

Nov. 6, 1990 Survey by Paul N. Brown, L.S. #33134 with Rowe Eng. Inc., recorded in Liber 609 on Pages 421, 422 & 423, Tuscola County records. No mention of object found or set.  
 N40°E 37.51' set rod #33134 in road shoulder.  
 N45°W 35.75' set rod #33134 in road shoulder.  
 S45°W 32.91' set rod #33134 in road shoulder.  
 N01°54'59"E 131.01' SW cor. Sec. 30, T11N-R8E.

Aug. 14, 1991 Survey by Jack N. Owens, L.S. #20709 with Rowe Eng. Inc., recorded in Liber 628 on Pages 742 through 745, Tuscola County records. Found 5/8" rerodin mon. box. Accessories same as Liber 609 on Pages 421, 422 & 423.

