

**SURVEY &
REMONUMENTATION**

APR 25 1995

COMMISSION

COPY

1994 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. _____
FILING NO. # 66
TUSCOLA TWP.
94 DEC - 7 PM 4: 26
VIRGINIA M. McCLAREN
TUSCOLA COUNTY
REGISTER OF DEEDS

For corners in Tuscola Township

Tuscola (County)	Located In:	Corner Code ##
1. Public Land Survey	T 11N R 7E	M-12
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Kenneth D. Dunton, in a field survey on Oct. 30, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1821 G.L.O. Notes May 6, 1976 Land Cor. Rec. Cert. filed on Page 25 of Tuscola
Joseph Wampler, D.S. Twp. by Arthur H. Leach, L.S. #7236. Found 1/2" re-rod, cap #11192.
Set 1/4 Sec. Post N10°E 38.45' to E. bridge rail pipe.
Maple 20 S 69 W 11 S40°E 41.15' to spike SW side triple balsam.
Beech 7 N 55 E 17 N50°W 34.28' to W. bridge rail pipe.
Note: The above data may be in error. No bridge at this location.
See following L.C.R.C. Page 24 from field survey on May 10, 1976.

Section A continued on back of this form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" iron rod in monument box and accepted as the proper position of the corner.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed standard brass cap stamped corner M-12, T11N-R7E on 5/8" re-rod over 3/4" iron rod found in mon. box. Encased rod & brass cap in concrete in mon. box.
N89°19'W 35.85' fnd. #11192 tag & nail in S. face wood cor. post. Set T. C. Remon. tag & spike above.
N25°47'W 90.79' fnd. disk & spike in E. face p. pole. Set T. C. Remon. tag & spike above.
N24°35'E 79.54' fnd. 1/2" rod & cap #20709 at top of ditch bank.
S89°02'E 14.11' set 1/2 x 18" rod & cap #23503 in road shoulder.
N00°08'38"E 72.30' fnd. 1" iron rod in mon. box at apparent cor. A-12, T11N-R8E.

Signed by [Signature] Date _____
Surveyor's Michigan License No. 23503

APPROVED
12-05-94

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN. 1983



Section A continued:

May 10, 1976 Land Cor. Rec. Cert. filed on Page 24 of Tuscola Township by Arthur H. Leach, L. S. #7236. Set 3" "T" iron on occupied line to West on line between M-13 and M-11 West 34.0' to Cor. Post. S40°W 34.70' to 12" C.M.P. West 2.90' to painted C/L of road.

May 15, 1976 Survey by Arthur H. Leach, L.S. #7236, recorded in Liber 460 on Page 274, Tuscola County records. Set 3" "T" iron. West 34.0' Cor. Post. S40°W 34.7' 12" C.M.P.

July 26, 1979 Survey by Arthur H. Leach, L.S. #7236, recorded in Liber 499 on Page 993, Tuscola County records. Fnd. "T" iron. W-34.0' to Cor. Post. S 40°W 34.7' to 12" C.M.P. W-2.9' to painted centerline road.

October 11, 1982 Survey in Sec. 31, T11N-R8E by Richard R. Boldt, L.S. #28405, recorded in Liber 536 on Page 1320, Tuscola County records. Fnd. "T" iron flush w/pavement at E 1/4 cor. Sec. 36, T11N-R7E, South 72.27' of R.R. spike fnd. at West 1/4 cor. Sec. 31, T11N-R8E.

August 26, 1987 Survey by Brian D. Ferguson, L.S. #26454, recorded in Liber 575 on Page 1173, Tuscola County records. "T" iron. W-34.0'-corner post, S40°W 34.7'-12' CMP, W. 2.9' painted C.L. road.

Dec. 11, 1987 Survey by Brian D. Ferguson, L.S. #26454 recorded in Liber 578 on Page 729, Tuscola County records. Object and accessories same as Liber 575, Page 1173.

August 14, 1991 Survey in Sec. 31, T11N-R8E, by Jack N. Owens, L.S. #20709, recorded in Liber 628 on Pages 742 through 745, Tuscola County records. Fnd. 5/8" rod in mon. box. N30°W 90.72' fnd. nail/disk SE face p. pole. North 72.57' W 1/4 cor. Sec. 31, T11N-R8E. N25°E 79.56' fnd. rod/cap #20709. West 35.83' set nail/tag #11192 S. face wd. fen. post.

