

1999 REMONUMENTATION PROGRAM  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

**COPY**

RECEIVED FOR RECORDS  
 USER NO. \_\_\_\_\_ PAGE NO. \_\_\_\_\_  
 FILE NO. # 109  
 99 DEC 21 PM 3:41  
 TUSCOLA COUNTY  
 REGISTER OF DEEDS

For corners in Vassar Township

<u>Tuscola</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T11N R8E	K-9
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Lionel Roy Emery  
 I, P.S. #24593, in a field survey on July 16, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

June, 1822 G.L.O. notes, Joseph Fletcher, D.S. Set corner to Secs. 23, 24, 25 & 26, Beech 12" S80°W 10 links, Hemlock 10" S70°E 10 links. March 17, 1892 Survey of Sec. 25 by G. B. Felton, County Surveyor, set from measurements, Beech 15" S15°W 219 links, Pine 7" N48 1/2°W 141 links. July 3, 1896 Survey of Sec. 23 by Edward L. Teskey, County Surveyor, established proportionate distance by Felton, Beech 14" S17 1/2°W 218 3/4 links, Pine 8" N50 3/4°W 141 1/4 links. April 8, 1898 Survey of Sec. 24 by G. B. Felton, County Surveyor, prev. set, Beech 15" S15°W 219 links, Pine 7" N48 1/2°W 141 links. Dec. 1, 1898 Survey of Sec. 26 by Edward L. Teskey, County Surveyor, set by John A. Teskey.

Sec. A con't on back of form

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found "T" iron in monument box and accepted same as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


Removed "T" iron & perpetuated with 5/8" iron rod and standard brass cap stamped K-9, T11N-R8E. Encased rod & cap in concrete in monument box.  
 N45°E 43.65' set remon. tag & nail in NW face tele. pole (fnd. nail & cap SW face).  
 S25°E 88.70' set remon. tag & nail in NE face 8" Maple in Maple clump.  
 S60°W 73.81' set remon. tag & nail in NW face Power Pole (fnd. nail & cap in NE face).  
 N45°W 50.82' set remon. tag & nail over #37276 tag in E. face 30" White Pine.

Due to the untimely illness of Mr. Emery, I, Kenneth D. Dunton, P.S. #23503 have reviewed Mr. Emery's field notes and have prepared this form.

Signed by [Signature]  
 Surveyor's Michigan License No. 23503

Date 12-13-99

APPROVED  
 12-13-99  
 KML  
 RLB  
 DMJ



# COPY

Sec. A Con't.

Feb., April & Sept., 1971 L.C.R.C. Page 12 by David T. Rowe, P.S. #11192, found P.K. nail in asphalt, N40°E 43.24' nail & cap in P. Pole, S70°E 36.58' nail & cap in 8" tree, S50°W 73.24' nail & cap in P. Pole. July 20, 1971 Survey L-1, P-530 & 531 by David T. Rowe, P.S. #11192, "T" iron, accessories same as L.C.R.C. Page 12. Jan. 4, 1974 Survey L-438, P-791 & 792 by David T. Rowe, P.S. #11192, fnd. P.K. nail, accessories same as Survey L-1, P-530 & 531. Aug. 6, 1974 Survey L-445, P-735 by David T. Rowe, P.S. #11192, object and accessories same as Survey L-438, P-791 & 792. May 30, 1975 Survey L-452, P-652 through 655 by James A. Beck, P.S. #21559, same object and accessories as Survey L-445, P-735. May 12, 1977 Survey L-474, P-248 & 249 and April 18, 1977 Survey L-474, P-260 & 261 by Kenneth D. Dunton, P.S. #23503 (with Rowe Eng.), same object and accessories as Survey L-452, P-652 through 655 with the addition of S40°W 65.10' to 6" Cedar tree. June 7, 1978 Survey L-488, P-875 & 876 by Kenneth D. Dunton, P.S. #23503 (with Rowe Eng.), object and accessories same as Survey L-452, P-652 through 655. June 30, 1978 Survey L-530, P-81 & 82 by David T. Rowe, P.S. #11192, object and accessories same as Survey L-452, P-652 through 655. June 12, 1985 Survey L-551, P-1124 & 1125 by Anne E. Wilson, P.S. #30107, found "T" iron in asphalt, N45°W 50.61' face 2" White Pine, N30°E 43.36' nail & cap in Power Pole, S50°E 46.22' center top cable closure, S45°W 41.15' center top 6" double stump. March 3, 1997 Survey L-736, P-906 & 907 by Jonathan M. Field, P.S. #37276, found T-iron in mon. box, N40°W 50.84' nail & tag #37276 in E. face 30" Pine, N45°E 43.37' nail & bottle cap in S. face T. Pole, S20°E 85.44' nail & tag #37276 in W. face 12" Poplar, S65°W 73.31' nail & bottle cap in NE face P. Pole.

