

**SURVEY &
REMONUMENTATION**

COPY

FEB 08 2001

SECTION

**2000 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74,
Mich. P.A. 1970**

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. _____
FILE NO. **#120 Vassar**

00 DEC 19 PM 1:35

Gregory M. Jensen
TUSCOLA COUNTY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in: VASSAR TWP.

Tuscola Located In: Corner Code #
(County)

- 1. Public Land Survey T 11N R 8E L-3
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R
in section S _____ T _____ R
- 3. Miscellaneous S _____ T _____ R
Property in Sec. S _____ T _____ R
- 4. Lot No. _____, Recorded Plat
- 5. Private Claims

	B	C	D	E	F	G	H	I	J	K	L
1											
2	6		5		4		3		2		1
3											●
4	7		8		9		10		11		12
5											
6	18		17		16		15		14		13
7											
8	19		20		21		22		23		24
9											
10	30		29		28		27		26		25
11											
12	31		32		33		34		35		36
13											

I, Kari M. Lohela, in a field survey on October 26, 20 00 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1822 G.L.O., JOSEPH FLETCHER, D.S., SET ¼ SECTION POST, BEECH 12 N 10 E 12, HEMLOCK 18 S 46 W 24

SEPT. 30, 1977, LCRC P.46 VASSAR TWP., KENNETH DUNTON, PS 23503, FOUND NOTHING FROM LARGE EXCAVATION. SET ON STRAIGHT LINE BETWEEN NE & NW CORNERS AND ON EXTENSION OF FENCE LINE SOUTH. CORNER IS APPROX. CENTERLINE OF OLD TRAIL EAST & WEST (O'BRIEN ROAD). SET 5/8" RE-ROD. OAK HUB AND STEEL FENCE POST NEXT TO IT. S10°W 34.55' RLS 11192 TAG IN 3" MAPLE, N05°E 17.10' RLS 11192 TAG IN 6" MAPLE, N05°W 39.20' RLS 11192 TAG IN 2" MAPLE, NORTH 31.25' RLS 11192 TAG IN WOOD FENCE POST.

AUG. 17, 1984, SURVEY L.546 PP.756-758, DAVID ROWE, PS 11192, FOUND SAME OBJECT AND ACCESSORIES AS LCRC P.46 VASSAR TWP.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 5/8" REBAR. RECOVERED 2 ACCESSORIES WHICH INDICATE THAT 5/8" REBAR IS IN SAME POSITION AS SURVEY AND LCRC CITED ABOVE.

ACCEPTED 5/8" REBAR AS BEST AVAILABLE EVIDENCE OF ORIGINAL CORNER POSIITON.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REMOVED 5/8" REBAR AND SET 36" CONCRETE MONUMENT WITH STANDARD BRASS CAP STAMPED L-3, T11N-R8E
NORTH 1.0' SET CARSONITE POST
N35°E 7.90' SET REMON TAG & NAIL IN NE FACE OF 4" OAK
S40°E 45.67' SET REMON TAG & NAIL IN NE FACE OF 8" TREE
S40°W 19.12' SET REMON TAG & NAIL IN SE FACE OF 4" BOX ELDER
WEST 32.30' SET REMON TAG & NAIL IN N. FACE OF 6" POPLAR
N10°W 39.44' SET REMON TAG & NAIL BELOW FOUND NAIL & TAG IN SE FACE OF 4" MAPLE

REMONUMENTATION

FEB 08 2001

SECTION

L-3 T11N-R8E

Signed by

Kari M. Loehela

Date 12/13/00

APPROVED BY TUSCOLA COUNTY
REMONUMENTATION PEER GROUP

12/13/2000

*AKD
MWP
RKB*

Surveyor's Michigan License No. 44289

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975

REVISED JAN., 1983
REVISED OCT., 1995

