

FEB 08 2001

COPY

SECTION

**2000 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74,
Mich. P.A. 1970

For corners in: VASSAR TWP.

Tuscola Located In:
(County)

Corner Code #

1. Public Land Survey T 11N R 8E L-5
 T _____ R _____
 T _____ R _____
 T _____ R _____
2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat

5. Private Claims

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. _____
FILE NO. #117 Vassar
00 DEC 19 PM 1:34
Ann M. Johnson
TUSCOLA COUNTY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6			5		4		3		2		1
3												
4	7			8		9		10		11		12
5												
6	18			17		16		15		14		13
7												
8	19			20		21		22		23		24
9												
10	30			29		28		27		26		25
11												
12	31			32		33		34		35		36
13												

I, Kari M. Lohela, in a field survey on October 26, 20 00 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1822 G.L.O., JOSEPH FLETCHER, D.S., SET ¼ SECTION POST, SUGAR 20 N 67 W 16, HEMLOCK 20 N 15 E 20

JULY 26, 1974, SURVEY L.475 P.130, ROBERT MITCHELL, PS 6936, SET ½" RE-ROD, S30°W 82.2' POWER POLE, NORTH 141.5' POWER POLE, N50°W 54.3' 10" CEDAR

JULY 12, 1977, SURVEY L.477 PP.864-867, KENNETH DUNTON, PS 23503, FOUND ½" RE-ROD SURROUNDED BY STONES, NORTH 141.45' DISC IN P.P., N10°E 63.38' RLS TAG IN 5" PINE, S50°W 93.55' RLS TAG IN 36" WEEPING WILLOW

JULY 13, 1977, SURVEY L.481 PP. 636-637, KENNETH DUNTON, PS 23503, NO MENTION OF OBJECT OR ACCESSORIES

SEPT. 30 1977, LCRC P.46 VASSAR TWP., KENNETH DUNTON, P.S. 23503, FOUND ½" RE-ROD 10" DEEP SURROUNDED DY STONES ON OLD LAND LINE NORTH, RAISED WITH ½" RE-ROD, N10°E 63.38' RLS 11192 TAG IN 5" PINE, S50°W 93.55' RLS 11192 TAG IN 36" WEEPING WILLOW, S50°E 112.65' RLS 11192 TAG IN 9" COTTONWOOD, WEST 30'± TO FENCE LINE SOUTH, SOUTH 5'± TO C/L NEW ROAD BED EAST & WEST

MAY 28, 1981, SURVEY L.567 PP.1375-1376, A.F. MILLER, PS 12024, FOUND IRON, NORTH 141.45' P.P., N10°E 63.38' RLS TAG IN 5" PINE, S50°W 93.55' RLS TAG IN 36" WEEPING WILLOW, S50°E 112.65' 9" COTTONWOOD

APRIL 23, 1982, SURVEY L.526 PP.5-6, RICHARD BOLDT, PS 23405, FOUND SAME OBJECT AND ACCESSORIES AS SURVEY L.477, PP.864-867

JUNE 28, 1984, SURVEY L.543 P.22, KENNETH DUNTON, PS 23503, FOUND SAME OBJECT AND ACCESSORIES AS SURVEY L.477, PP.864-867

FEB. 20, 1995, SURVEY L.670 PP.876-877, JONATHAN FIELD, PS 37276, FOUND ½" ROD, S35°W 41.55' SET NAIL W/FLAG IN W. FACE 8" POPLAR, S43°W 44.91' SET ½" ROD W/CAP #20709, N05°E 63.30' SET NAIL W/FLAG IN E. FACE 10" PINE, S50°E 62.73' SET P.K. NAIL IN NE FACE FENCE POST

