

COPY

1999 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Vassar Township

<u>Tuscola</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T11N R8E	L-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

RECEIVED FOR RECORD
 LIBER NO. _____ PAGE NO. _____
 FILE NO. #110
 99 DEC 21 PM 3:41
 VASSAR TWP
 TUSCOLA COUNTY
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Lionel Roy Emery
 P.S. #24593, in a field survey on July 21, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

June, 1822 G.L.O. Notes, Joseph Fletcher, D.S. Set 1/4 section post, Beech 24" S47°E 24 links, Beech 10" S69°W 19 links. March 17, 1892 Survey of Sec. 25 by G. B. Felton, County Surveyor, set from measurements, Cedar Post & crockery at corner. No accessories given. April 8, 1898 Survey of Sec. 24 by G. B. Felton, County Surveyor, previously set, C.P., iron ring, beer bottle & crockery at corner. No accessories given. July 20, 1971 Survey L-1, P-530 & 531 by David T. Rowe, P.S. #11192, found corner post & set "T" iron, N20°E 22.1' 10" Poplar, S80°E 45.3' 12" tree, S45°W 24.17' 8" Poplar. Sec. A con't on back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found "T" iron at SE face cedar post and accepted same as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Removed "T" iron & perpetuated with 36" concrete monument with standard brass cap stamped L-9, T11N-R8E. Set carsonite post 1.0' west. East 19.94' set remon. tag & nail in 8" Poplar. South 18.40' set remon. tag & nail in 6" Maple. S80°W 9.62' set remon. tag & nail in Cherry. N05°W 28.71' set remon. tag & nail in 8" Poplar.

Due to the untimely illness of Mr. Emery, I, Kenneth D. Dunton, P.S. #23503, have reviewed Mr. Emery's field notes and have prepared this form.

Signed by [Signature]
 Surveyor's Michigan License No. 23503

Date 12-13-99
 KENNETH D. DUNTON
 LAND SURVEYOR
 #23503
 STATE OF MICHIGAN
 MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS
 JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN. 1983
 REVISED OCT. 1985

APPROVED
12-13-99 KML
 RUB
 JMG