

FEB 08 2001

COPY

SECTION

2000 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich.
P.A. 1970

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. _____
FILE NO. #114 Vassar

00 DEC 19 PM 1:34

Gray-Melvin
TUSCOLA COUNTY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in: VASSAR TWP.

Tuscola Located In: Corner Code #
(County)

- 1. Public Land Survey T 11N R 8E K-7
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Sec. 2

- 4. Lot No. _____, Recorded Plat
- 5. Private Claims

I, Kari M. Lohela, in a field survey on October 26, 20 00 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6			5			4			3		2
3												
4	7			8			9			10		11
5												
6	18			17			16			15		14
7												
8	19			20			21			22		23
9												
10	30			29			28			27		26
11												
12	31			32			33			34		35
13												

- A. Description of original monument and accessories and/or subsequent restoration:
1822 G.L.O. NOTES, FLETCHER, D.S., SET CORNER TO SECS. 13, 14, 23 & 24.
NUMEROUS SUBSEQUENT SURVEYS CITED IN 1999 REMONUMENTATION LCRC, P. 112 VASSAR TWP.
1999 REMONUMENTATION LCRC, P.112 VASSAR TWP., DUNTON, PS 23503, SET 5/8" BAR AND BRASS CAP STAMPED K-7, T11N, R8E, IN MON. BOX.
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND BRASS CAP K-7 AND BAR ENCASED IN CONC., LAYING IN DITCH EAST OF FORMER POSITION.
ALSO FOUND 3/4" BAR IN MONUMENT BOX ON CENTERLINE OF SHERIDAN ROAD. RECOVERED ALL 4 ACCESSORIES FROM 1999 REMONUMENTATION LCRC, SECTION C., WHICH INDICATES THAT POSITION OF 3/4" BAR IS WITHIN 0.1' OF POSITION OCCUPIED BY FORMER CORNER K-7.
RESECTED POSITION OF CORNER K-7 FROM RECOVERED ACCESSORIES.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
RAISED 3/4" BAR WITH 1/2" BAR AND STANDARD BRASS CAP STAMPED K-7, T11N-R8E. ENCASED BAR AND CAP IN CONCRETE IN EXISTING MONUMENT BOX.
N30°E, 87.41' EXPOSED SW REROD IN TOP OF CONC. R.O.W. MARKER
EAST, 34.54' FOUND REMON. TAG & NAIL OVER MSHD TAG IN N. FACE OF UTILITY POLE
WEST, 60.02' FOUND REMON. TAG & NAIL OVER MSHD TAG IN N. FACE OF UTILITY POLE
S20°E, 103.12' FOUND REMON. TAG & NAIL OVER NAIL IN SW FACE OF UTILITY POLE