

OCT 20 1994

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

1994 REMONUMENTATION PROGRAM

For corners in **COMMERCIAL** Fremont Twp. TUSCOLA (County)

Located in:

Corner Code #

- 1. Public Land Survey T 11N R 09E C-13
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

REGISTER OF DEEDS stamp area with 'COPY' watermark and 'VIRGINIA M. McLELLAN TUSCOLA COUNTY REGISTER OF DEEDS' text.

- 4. Lot No. Recorded Plat
5. Private Claims

I, JONATHAN M. FIELD, in a field survey on JULY 14 19 94 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13 containing numbers 1-36.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration: 1834 GLO; PARKE, D.S.; SET POST; BEECH 16 N64E 9LKS., HEMLOCK 13 N75W NO DIST. GIVEN 1891 FELTON, C.S.; PREV. SET FROM B.T.'S; CEDAR POST & CROCKERY; PINE 36 S67E 57LKS. 1970 ROWE ENG.; DALLAS; SURVEY FOR DAVID KONTAK JOB NO. C-0024-70; NOTES SHOW T-IRON SET AT C/L ROAD 33' E. OF FENCE; NW 128.7' P.POLE, NW 39.2' ANCHOR POST, NE 44.5' 30" STUMP, SE 93.3' ANCHOR POST 1972 ROWE ENG.; ROWE, P.S.#11192; SURVEY L.2, PG.45-46; FND. T-IRON; N05°W 128.56' ROWE TAG P.P N50°W 39.94' NAIL IN COR POST, S70°E 93.77' NAIL IN COR POST 1972 ROWE, P.S.#11192; LCRC 25; FND. T-IRON; SAME WITS AS 1972 SURVEY 1973 ROWE ENG.; ROWE, P.S.#11192; SURVEY L.437, PG.348; FND. T-IRON; SAME WITS AS 1972 SURVEY 1977 LEACH ENG., LEACH, P.S.#7236; SURVEY FOR MCLEOD REALTY FILE NO. C-77-123; FND. T-IRON B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: 1994 ROWE ENG. - FIELD, P.S.#37276; FND 1/2" ROD 3.5' E. OF C/L - C/L OF GRAVEL ROADS E-W-N 2 PREVIOUS WITNESSES INDICATE THAT 1/2" ROD IS IN SAME POSITION AS 1970 ROWE ENG. IRON ACCEPTED 1/2" ROD AS BEST EVIDENCE OF ORIGINAL CORNER POSITION

SEE ALSO BACK OF THIS FORM

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: C-13 REMOVED ROD, SET STANDARD MONUMENT (5/8"X36" ROD W/ BRASS CAP IN CONC.) N10°W, 127.79' FND NAIL W/TAG #11192 IN S. FACE P.POLE N14°W, 90.15' SET NAIL W/REMON TAG IN E. FACE 8" ASH N54°W, 39.30' SET NAIL W/REMON TAG IN SW FACE FENCE POST S42°W, 31.47' TOP CENTER OF PHONE RISER N53°E, 49.47' TOP CENTER OF PHONE RISER S46°E, 34.68' SET 1/2" ROD W/CAP #37276



Signed by Jonathan M. Field Date 9-2-94 Surveyor's Michigan License No. 37276

APPROVED stamp with date 8-29-94 and signature.

SECTION A.

1977 LEACH; SAME WITS AS 1972 REI SURVEY.

1993 CORNERSTONE; BONNO, P.S.#32332; SURVEY FOR TIMOTHY MCLEOD DATED 6-10-93; SET 1/2" ROD; N20W 128.30' P.POLE, N45E 49.00' MBT BOX, S45E 31.35' MBT BOX, N45W 39.31' CORNER POST, S80E 91.6' ANCHOR POST

