

OCT 26 1994

COMMISSIONER

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970
1994 REMONUMENTATION PROGRAM

For corners in Fremont Twp.
TUSCOLA
(County)

Located In:

Corner Code #

1. Public Land Survey	T	11N	R	09E	D-13
	T		R		
	T		R		
	T		R		
2. Property Controlling In Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

COPY

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. _____
FILING NO. # 70
FREMONT TWP.
94 OCT 10 AM 8:49
VIRGINIA M. McLAUREN
TUSCOLA COUNTY
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, JONATHAN M. FIELD, in a field survey on JULY 14 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1834 GLO; PARKE, D.S.; SET POST; BEECH 16 N82E 40LKS., BEECH 16 N88 1/2W 32 1/2 LKS.
- 1891 FELTON, C.S.; FROM B.T.'S IN 1875; NO OBJECT STATED; BEECH 8 N83E 169LKS., ELM 7 N 13 1/2 E 205LKS.
- 1972 ROWE ENG.; ROWE, P.S.#11192; SURVEY L.2, PG.45-46; FND 1/2" ROD; N40°W 70.39' NAIL IN P.P. N60°E 35.30' NAIL IN COR POST, N50°W 51.55' RD SIGN POST
- 1972 ROWE, P.S.#11192; LCRC 25; FND 1/2" ROD; WITS SAME AS 1972 SURVEY
- 1973 ROWE ENG.; ROWE, P.S.#11192; SURVEY L.437, PG.348; 1/2" ROD; SAME WITS AS 1972 SURVEY
- 1977 LEACH ENG., LEACH, P.S.#7236; SURVEY L.478, PG.01; FND RE-ROD; SAME WITS AS 1972 SURVEY
- 1977 LEACH ENG.; LEACH, P.S.#7236; SURVEY L.481, PG.499; FND RE-ROD; SAME WITS AS 1972 SURVEY
- 1978 LEACH ENG., LEACH, P.S.#7236; SURVEY L.489, PG.764; FND 3/8" ROD; SAME WITS AS 1972 SURVEY

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1994 ROWE ENG. - FIELD, P.S.#37276; FND 1/2" ROD 2'S. OF C/L OF GRAVEL ROAD E-W & ON C/L EXT. OF ASPH. ROAD TO N. 3 PREVIOUS WITNESSES INDICATE THAT 1/2" ROD IS IN SAME POSITION AS 1972 ROWE ENG. IRON

ACCEPTED 1/2" ROD AS BEST EVIDENCE OF ORIGINAL CORNER POSITION

SEE ALSO BACK OF THIS FORM

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-13 REMOVED ROD, SET STANDARD MONUMENT (5/8"X36" ROD W/ BRASS CAP IN CONC.)
- N55°W, 51.60' CENTER OF ROAD SIGN POST
- N44°W, 69.94' SET NAIL W/REMON TAG IN ENE FACE P. POLE
- N53°E, 35.45' SET NAIL W/REMON TAG IN W. FACE FENCE CORNER POST (LEANS NE'LY)
- S64°E, 50.60' SET NAIL W/REMON TAG IN SW FACE TWIN 8" ELM
- S03°W, 18.12' E. EDGE OF E. SIGN POST LEG
- S72°W, 35.37' SET 1/2" ROD W/ CAP #37276

Signed by Jonathan M. Field Date 9-2-94
Surveyor's Michigan License No. 37276



APPROVED
8-29-94

Handwritten initials and signatures.

SECTION A.

- 1981 LEACH ENG.; LEACH, P.S.#7236; SURVEY L.518,PG.131; FND. 1/2" RE-ROD; SAME WITS AS 1972 REI SURVEY.
- 1981 LEACH ENG.; LEACH, P.S.#7236; SURVEY L.518,PG.133-134; FND. 1/2" RE-ROD; SAME WITS AS 1972 REI SURVEY.
- 1993 CORNERSTONE; BONNO, P.S.#32332; SURVEY FOR TIMOTHY MCLEOD DATED 6-10-93; NO OBJECT STATED; REFERS TO L.478,PG.01 (1977 LEACH SURVEY)

